

THE ARCHITECTS' JOURNAL



standard contents

every issue does not necessarily contain
all these contents, but they are
the regular features which
continually recur

NEWS and COMMENT

Astragal's Notes and Topics

Letters

News

Diary

Societies and Institutions

TECHNICAL SECTION

Information Sheets

Information Centre

Current Technique

Working Details

Questions and Answers

Prices

The Industry

CURRENT BUILDINGS

Major Buildings described:

*Details of Planning, Construction,
Finishes and Costs*

Buildings in the News

Building Costs Analysed

*Architectural Appointments
Wanted and Vacant*

No. 3184/5]

[Vol. 123

THE ARCHITECTURAL PRESS

9, 11 and 13, Queen Anne's Gate, Westminster,
S.W.1. 'Phone: Whitehall 0611

Price 1s. 0d.

Registered as a Newspaper.

★ A glossary of abbreviations of Government Departments and Societies and Committees of all kinds, together with their full address and telephone numbers. The glossary is published in two parts—A to I one week, I to Z the next. In all cases where the town is not mentioned the word LONDON is implicit in the address.

IHVE	Institution of Heating and Ventilating Engineers. 49, Cadogan Square. Sloane 1601/3158
IIBDID	Incorporated Institute of British Decorators and Interior Designers. 100 Park Street, Grosvenor Square, W.1. Mayfair 7086
ILA	Institute of Landscape Architects. 12, Gower Street, W.C.1. Museum 1783
I of Arb	Institute of Arbitrators. Hastings House, 10, Norfolk Street, Strand W.C.2. Temple Bar 4071
IOB	Institute of Builders. 48, Bedford Square, W.C.1. Museum 7197
IQS	Institute of Quantity Surveyors, 98, Gloucester Place, W.1. Welbeck 1859
IR	Institute of Refrigeration. Dalmeny House, Monument Street, E.C.3. Avenue 6851
IRA	Institute of Registered Architects. 47, Victoria Street, S.W.1. Abbey 6172
ISE	Institute of Structural Engineers. 11, Upper Belgrave Street, S.W.1. Sloane 7128
LDA	Lead Development Association. Eagle House, Jermyn Street, S.W.1. Whitehall 7264/4175
LMBA	London Master Builders' Association. 47, Bedford Square, W.C.1. Museum 3891
LSPC	Lead Sheet and Pipe Council. Eagle House, Jermyn Street, S.W.1. Whitehall 7264/4175
MAFF	Ministry of Agriculture, Fisheries and Food. Whitehall Place, S.W.1. Trafalgar 7711
MARS	Modern Architectural Research Group (English Branch of CIAM). Secretary: Trevor Dannatt, A.R.I.B.A., 71, Blandford Street, W.1. Welbeck 4713
MOE	Ministry of Education. Curzon Street House, Curzon Street, W.1. Mayfair 9400
MOH	Ministry of Health. 23, Savile Row, W.1. Regent 8411
MOHLG	Ministry of Housing and Local Government. Whitehall, S.W.1. Whitehall 4300
MOLNS	Ministry of Labour and National Service. 8, St. James' Square, S.W.1. Whitehall 6200
MOS	Ministry of Supply. Shell Mex House, W.C.2. Gerrard 6933
MOT	Ministry of Transport. Berkeley Square House, Berkeley Square, W.1. Mayfair 9494
MOW	Ministry of Works. Lambeth Bridge House, S.E.1. Reliance 7611
NAMMC	Natural Asphalte Mine Owners and Manufacturers Council. 94/98, Petty France, S.W.1. Abbey 1010
NAS	National Association of Shopfitters. 9, Victoria Street, S.W.1. Abbey 4813
NBR	National Buildings Record. 31, Chester Terrace, Regent's Park, N.W.1. Welbeck 0619
NCBMP	National Council of Building Material Producers. 10 Storey's Gate, S.W.1. Abbey 5111
NEFMAI	National Employers Federation of the Mastic Asphalt Industry. 21, John Adam Street, Adelphi, W.C.2. Trafalgar 3927
NFBTE	National Federation of Building Trades Employers. 82, New Cavendish Street, W.1. Langham 4041/4054
NFBTO	National Federation of Building Trades Operatives. Federal House, Cedars Road, Clapham, S.W.4. Macaulay 4451
NFHS	National Federation of Housing Societies. 12, Suffolk St., S.W.1. Whitehall 1693
NHBRC	National House Builders Registration Council. 82, New Cavendish Street, W.1. Langham 4341
NPL	National Physical Laboratory. Head Office, Teddington. Molesey 1380
NRDB	Natural Rubber Development Board. Market Buildings, Mark Lane, E.C.3. Mansion House 9383
NSAS	National Smoke Abatement Society. Palace Chambers, Bridge Street, S.W.1. Trafalgar 6838
NT	National Trust for Places of Historic Interest or Natural Beauty. 42, Queen Anne's Gate, S.W.1. Whitehall 0211
PEP	Political and Economic Planning. 16, Queen Anne's Gate, S.W.1. Whitehall 7245
RCA	Reinforced Concrete Association. 94, Petty France, S.W.1. Abbey 4504
RIAS	Royal Incorporation of Architects in Scotland. 15, Rutland Square, Edinburgh. Fountainbridge 7631
RIBA	Royal Institute of British Architects. 66, Portland Place, W.1. Langham 5721
RICS	Royal Institution of Chartered Surveyors. 12, Great George St., S.W.1. Whitehall 5322/9242
RFAC	Royal Fine Art Commission. 5, Old Palace Yard, S.W.1. Whitehall 3935
RS	Royal Society. Burlington House, Piccadilly, W.1. Regent 3335
RSA	Royal Society of Arts. 6, John Adam Street, W.C.2. Trafalgar 2366
RSH	Royal Society of Health. 90, Buckingham Palace Road, S.W.1. Sloane 5134
RIB	Rural Industries Bureau. 35, Camp Road, Wimbledon, S.W.19. Wimbledon 5101
SBPM	Society of British Paint Manufacturers. Grosvenor Gardens House, Grosvenor Gardens, S.W.1. Victoria 2186
SE	Society of Engineers. 17, Victoria Street, Westminster, S.W.1. Abbey 7244
SFMA	School Furniture Manufacturers' Association. 30, Cornhill, London, E.C.3. Mansion House 3921
SIA	Society of Industrial Artists. 7, Woburn Square, London, W.C.1. Langham 1984/5
SIA	Structural Insulation Association. 32, Queen Anne Street, W.1. Langham 7616
SNHTPC	Scottish National Housing. Town Planning Council. Hon. Sec., Robert Pollock, Town Clerk, Rutherglen.
SPAB	Society for the Protection of Ancient Buildings. 55, Great Ormond Street, W.C.1. Holborn 2646
TCPA	Town and Country Planning Association. 28, King Street, Covent Garden, W.C.2. Temple Bar 5006
TDA	Timber Development Association. 21, College Hill, E.C.4. City 4771
TPI	Town Planning Institute. 18, Ashley Place, S.W.1. Victoria 8815
TTF	Timber Trades Federation. 75, Cannon Street, E.C.4. City 5040
WDC	War Damage Commission. 6, Carlton House Terrace, S.W.1. Whitehall 4341
ZDA	Zinc Development Association. 34, Berkeley Square, W.1. Grosvenor 6636

...you've
got
to
hand
it
to
MILLS

CONCRETE FORMWORK

FOR SAFETY, SERVICE AND SATISFACTION

MILLS SCAFFOLD CO. LTD., (A Subsidiary of Guest, Keen & Nettlefolds Ltd.)

Head Office: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6. (RIVERSIDE 5026/9)

Agents and Depots: BELFAST • BIRMINGHAM • BOURNEMOUTH • BRADFORD • BRIGHTON • BRISTOL • CANTERBURY • CARDIFF • COVENTRY • CROYDON • DUBLIN • GLASGOW • HULL • ILFORD
LIVERPOOL • LOWESTOFT • MANCHESTER • MIDDLESBROUGH • NEWCASTLE • NORWICH • PLYMOUTH • PORTSMOUTH • PRESTON • READING • SHIPLEY • SOUTHAMPTON • SWANSEA • YARMOUTH

ON
Ltd.)
26/9)
ILFORD
ARMOUTH

Operation Rescue



Hull Housing Committee's Experiment

The Housing Committee of Kingston-upon-Hull recently decided to take advantage of the Housing Repairs and Rents Act, 1954, to effect improvements to a number of their older houses lacking modern heating and sanitary facilities.

An important factor was that the tenants were able to remain in their homes whilst the work was actually being carried out, and there was thus no need to provide temporary accommodation elsewhere.

In one instance an existing room is converted into a bathroom, whereas in the other houses the bathroom has been added as an external structure by converting the 'out-houses'. Each bathroom has been fitted with a "Standard" porcelain enamelled cast-iron bath, vitreous china lavatory basin, and closet with high-level cistern.

The old-fashioned fireplace has been replaced with an Ideal No. 2C Neofire. This provides the domestic hot water supply from an Ideal 'Indirect' Cylinder installed in an existing bedroom cupboard converting it into an airing chamber. In addition the Ideal Neofire provides 'Background' heating by means of Ideal hot-water radiators fitted into two other rooms.

The old-fashioned sink in the kitchen has been replaced with the more hygienic "Standard" porcelain enamelled cast-iron "Hostess" Sink.

The result is a new lease of life for the property, bringing increased happiness and comfort to the appreciative and delighted tenants at the cost of a small increase in rent which they are very willing to pay.

The Heating and Sanitary Equipment selected by the Hull Housing Committee for this experimental scheme was manufactured by

IDEAL BOILERS & RADIATORS LTD.

who were pleased to be given the opportunity of co-operating in this successful project.

A fully explanatory booklet is available on request.



ONLY **POLYFILLA** STANDS UP TO THIS AMAZING TEST!

NEW DISCOVERY

POLYFILLA

THE CELLULOSE FILLER WITH THE PERFECT POSITIVE BOND

POLYFILLA is an amazing NEW discovery. IT DOES NOT SHRINK OR EXPAND AND WILL NOT BECOME LOOSE OR SHAKE OUT. It BONDS itself to surfaces with strong elastic cellulose adhesion as it does NOT depend solely on mechanical cling of easily shattering plaster crystals. It is made by the makers of POLYCELL.



For plaster or brick—filling cracks or holes, large or small. Brush out. Slightly damp surface. Press Polyfilla well home so as to fill crack or cavity completely in one application.



Use as a Putty. Forms a resilient bond between wood or metal and glass. Easy to work. Does not follow the knife.

UNIQUE POLYFILLA ADVANTAGES

- **PREPARE AS MUCH AS YOU NEED**—it will stay workable for an hour or more.
- **NO need to cut back** or enlarge crack. Only fillers which expand require "cutting back" to give anchorage. **POLYFILLA** holds firmly in place by strong positive cellulose adhesion.
- **Won't shake loose by vibration.** Use for gaps between plaster boards, behind door frames, skirting boards, between floorboards, etc.
- **Produces a perfectly self-sized surface.** Needs no SIZING, oiling in or shellacking. Decorate directly on to the self-sized surface—no hot spot.
- **Plugs woodwork.** No need to use dowels. Where old hinge-plates, locks, etc. have been removed from doors, **POLYFILLA** will plug large holes and adhere firmly to the wood.
- **Grain-filling before staining, varnishing or polishing**—**POLYFILLA** is ideal for all these purposes.
- **Easy to mix.**

When used for **EXTERIOR WORK** or in wet places (e.g. behind sinks) apply a coat of paint in the usual way.

PATENT Appln. No. 37343/54

ORDER YOUR STOCKS **NOW** FROM
POLYCELL PRODUCTS LTD.,

84 Albert Street, London, N.W.1

Positive Bond means that Polyfilla bonds itself to plaster, brick or wood with strong cellulose adhesion. Look at this ordinary brick. After a hammer blow, strong enough to break brick, **POLYFILLA STILL ADHERES** to both parts! Nails hammered in have not split or broken **POLYFILLA** away. Clear proof of **POSITIVE BOND**. Screws take the weight of ordinary household fixtures without further preparation.



There are three types
of **GYPROC Lath**
—the perfect base
for Paristone and
Gypstone Plasters

PLAIN

PERFORATED

INSULATING

A high degree of fire resistance is afforded by *plain GYPROC Lath* plastered with either Paristone or Gypstone, but for special purposes an even greater degree of fire protection can be obtained by using **GYPROC Perforated Lath**, plastered with Paristone.

Where thermal insulation is a specific requirement, **GYPROC Insulating Lath**, with a bright aluminium veneer on one side, should be used.

GYPROC Lath with its specially designed edges does not require scrimming before plastering.

All GYPROC Lath is supplied in bundles containing 6 sheets, easily carried by one man. Dimensions 16" wide, lengths 42", 48" and 54".

Write for leaflets P326 & P317.



Makers of PARISTONE Browning Plaster (Haird Unhaired and Metal Lathing Grades), PARISTONE Wall Finishing Plaster, CRETSTONE Concrete Bonding Plaster, GYPSTONE Board Finishing Plaster, GYPLITE Vermiculite Insulating Plaster (Undercoat and Finishing Grades).

GYPROC PRODUCTS LIMITED


Head Office: Singlewell Road, Gravesend, Kent. Telephone: Gravesend 4251-4. Telegrams: Gyproc, Gravesend. Glasgow Office: Gyproc Wharf, Shieldhall, Glasgow, S.W.1. Telephone: Govan 2141-3. Telegrams: Gyproc, Glasgow. Midland District Sales Office: East Leake near Loughborough. Telephone: East Leake 231. London Office: Bath House, 82 Piccadilly, London, W.1. Telephone: Grosvenor 4617-9.

LPI

Free House!



It wasn't supposed to be an invitation. The trouble is so many old locks do no more than just keep the door closed (and sometimes not even that) whilst real security measures are non-existent. The safest course if you value your property is to re-equip all important doors inside and out with the world's most reliable locks — YALE. There are YALE locks and padlocks to meet every security risk. Here is an example:




M.555 LEVER MORTICE DEADLOCK

The latest lock for keeping out the uninvited 'guest' from lock-up premises. Designed to meet insurance requirements, it is a 5-lever deadlock operable by key from both sides. Differs are obtainable on levers only and not by use of wards, making it extremely difficult to pick. Its steel reinforced deadbolt and 10" steel striking plate make it almost impossible to force. Available ex stock; literature on request.

Where there's a door there's a need for

YALE
REGISTERED TRADE MARK



CERAMIC TILES SAY 'WELCOME' - PERMANENTLY


This modern approach in ageless wall and floor material is just one more of the many ways in which architects are employing Ceramic Tiles.

Their unlimited combination of pattern, texture and colour fit the most ingenious conceptions of modern commercial interior and exterior wall and floor surfaces.

Ceramic

T I L E S

Glazed & Floor Tile Manufacturers' Association Federation House Stoke-on-Trent



Synthaprufe seals off building surfaces against weather

SYNTHAPRUFÉ is an all-purpose waterproofing, which contains rubber. Made from by-products of British coal, it is applied *cold* by brush to produce a strong elastic film that is highly resistant to moisture and remains flexible under all normal conditions.

Synthaprufe is extremely adhesive. This means that it forms a perfect, lasting seal over the whole of the surface to which it is applied.

AN IDEAL JOINTING

Almost any surface—wood, brick, metal, concrete or plaster—will take Synthaprufe; and with its unique ability to stick firmly, to remain flexible and to resist moisture, Synthaprufe

is widely recognized as a first-class material for all kinds of jointing.

A VERSATILE COMPOUND FOR BUILDERS

Besides being ideal for waterproofing and jointing, Synthaprufe makes a highly efficient damp course for walls, both inside and out, and is a recog-

nized treatment where damp is already present. It also makes a very effective sandwich layer in concrete subfloors; it is a completely reliable adhesive for fixing linoleum and wood-block floors; and it makes an excellent mechanical key for plaster finishes over old glazed or painted brick walls, as in hospitals and institutions.

SYNTHAPRUFÉ contains rubber



MANUFACTURED BY THE NATIONAL COAL BOARD

Synthaprufe is a product of British coal. Further details, and advice on any technical problem, will gladly be given on application to the National Coal Board, By Products, National Provincial Bank Buildings, Docks, Cardiff.



By courtesy of the County Borough of Burnley and
the main contractors Leonard Fairclough Ltd.

Architects: Messrs. Bradshaw, Gass & Hope
Sub-Contractors: Messrs. William Livesey & Sons (Blackburn) Ltd.

THE NEW BURNLEY POLICE HEADQUARTERS

ROYAL FLUSH

DOORS

Strength and dignity combine well in the design and construction of this imposing new building. But such features are not confined to its outward appearance... inside too, "Royal Flush" Doors offer similar characteristics. During the last twenty years these famous doors have been specified for many other newsworthy buildings. "Royal Flush" Doors are craftsman-made and can be supplied with solid or semi-solid cores in a wide variety of veneers. Send for full details and prices.

SOUTHERNS
— LIMITED —

HEAD OFFICE: BOLD SAW MILLS • WIDNES • TEL: WIDNES 2641

BRANCHES AT LONDON • GLASGOW • MANCHESTER • DUDLEY • HANLEY • BRISTOL AND KETTERING

Spans & Loads



FLOORS & ROOFS													
Depth	TYPICAL CROSS SECTIONS	Self Wt. per sq.ft.	Type	Superimp'd load lb./ft. ²	30 lb.	40 lb.	50 lb.	60 lb.	80 lb.	100 lb.	150 lb.	200 lb.	
5"		36 lb	C5 Incl. 2" Structural Screed on 3" Wood Wool Slab	Case 1	12' 6"	12' 0"	11' 6"	11' 3"	10' 3"	10' 0"	—	—	
5"		38 lb.		Case 2	13' 9"	13' 6"	13' 0"	12' 6"	11' 9"	11' 0"	—	—	
5"		40 lb		Case 3	—	—	—	13' 9"	13' 0"	12' 3"	—	—	
5"		42 lb		Case 4	—	—	—	—	—	13' 0"	—	—	
7"		35 lb	X7	Case 1	20' 6"	19' 6"	18' 8"	17' 9"	16' 5"	15' 3"	13' 3"	11' 11"	
7"		36 lb.	do.	Case 2	23' 8"	22' 5"	21' 8"	20' 5"	18' 11"	17' 8"	15' 4"	13' 9"	
7"		40 lb.	do	Case 3	25' 5"	24' 1"	23' 1"	22' 1"	20' 6"	19' 2"	16' 9"	15' 0"	
7"		42 lb.	do.	Case 4	—	26' 9"	25' 7"	24' 6"	22' 9"	21' 4"	18' 8"	16' 9"	
7"		60 lb	do	Case 5	—	—	—	—	—	—	25' 5"	23' 0"	
9"		47 lb	X9	Case 1	30' 5"	28' 10"	27' 10"	26' 6"	24' 9"	23' 2"	20' 4"	18' 4"	
9"		53 lb.	do.	Case 2	35' 4"	33' 8"	32' 4"	31' 0"	29' 1"	27' 3"	24' 5"	21' 8"	
10"		55 lb	I10	Case 1	36' 9"	35' 2"	33' 10"	32' 7"	30' 5"	28' 8"	25' 2"	23' 0"	
10"		60 lb.	do.	Case 2	41' 6"	39' 10"	38' 4"	37' 0"	34' 8"	32' 10"	29' 0"	26' 4"	

PIERHEAD LIMITED

SPEKE BOULEVARD, LIVERPOOL, 19
 Telephone - HUNTS CROSS 1311
 FAGGS LANE, FELTHAM, MIDDLESEX
 Telephone - FELTHAM 2555 & 3031

Moulding the future...

60 m.p.h. and up to 100 m.p.g. on a scooter streamlined like a space ship! Is this the materialisation of our childhood dream—or is it... yes, it is: yet another case of the future being moulded in

Fibreglass. How else could such sinewy strength be so adroitly shaped!

Pigmented polyester resin was reinforced with Fibreglass chopped strand mat and contact moulded in only *two* sections.

Hats off to the Harper Aircraft Company for their successful enterprise—and to the material that is inspiring more and more designers of today and planners of tomorrow!

Fibreglass have an FRP advisory service which is expert, confidential and free.




FIBREGLASS
TRADE MARK

the backbone of Reinforced Plastics



No need to climb to dizzy heights—



**You can tell at a touch
these doors are running
on KING Sliding Door Gear**

When sliding doors slide easily and obediently at a touch you can be almost sure they are running on **KING** gear. The high-precision engineering of **KING** Sliding Door Gear gives smooth, trouble-free performance year in, year out.

That's why there is such a strong preference for **KING** in factories, farms, garages

and houses. Straight folding or around-the-corner doors, there is a set of **KING** Sliding Door Gear for every size and type of job.

Architects and builders are invited to send for illustrated booklets showing the wide range and applications of **KING** Sliding Door Gear. Our experts are glad to advise on special installations.



SLIDING DOOR GEAR

Covered by British Patents

REGISTERED TRADE MARK

Write for Booklet 201 GEO. W. KING LIMITED, ARGYLE WORKS, STEVENAGE, HERTS. TEL: STEVENAGE 440


YOURS *for the Asking*

LEARN HOW TO:—
SPECIFY,
TEST,
USE,

SHERARDIZING

**ZINC ALLOY
RUST PROOFING CO. LTD.**

SHAKESPEARE STREET, WOLVERHAMPTON
TELEPHONE: WOLVERHAMPTON 20647/8
ALSO AT LONDON & ROCHDALE.



MAXIMUM CLEAR SPANS FOR SUPERLOAD OF 30 LB. PER SQ. FT.

(Allowance already made for self-weight and 26 lb. per sq. ft. finishes)

Concrete thickness	Hy-Rib alone		With rods		Minimum length to add to give adequate bearings for Hy-Rib sheets	Rod data—code used in table under "rods" heading
	28G	26G	26G	26G		
3"	6' 5"	7' 3"	7' 7"	a1	4'	Diameter:— a: $\frac{1}{2}$ " b: $\frac{3}{8}$ " c: $\frac{1}{4}$ " d: $\frac{3}{16}$ " e: $\frac{1}{8}$ "
3½"	6' 9"	7' 8"	9' 0"	a2		Spacing:— 1: 10½" crs. 2: 7" crs. 3: 3½" crs.
4"	7' 1"	8' 0"	10' 5"	b2		Lengths:—clear spans less 2' 0" (laid centrally)
4½"	7' 4"	8' 3"	11' 10"	e1	5'	
5"	7' 8"	8' 6"	13' 3"	e2		
5½"	7' 10"	8' 7"	14' 8"	c3	6'	
6"	8' 0"	8' 10"	15' 6"	d3		

HY-RIB SHEET DATA

Width of sheets is 10½ in. with ribs at 3½ in. centres.
Lengths are standardised:—26G, Hy-Rib: 6 to 16 ft. in 1 ft. increments
28G, Hy-Rib: 6 to 9 ft.

CONSTRUCTION DATA

1. All Hy-Rib sheets to be well interlocked and punched or wired together at 2' 0" centres along all side laps.
2. $\frac{1}{2}$ " dia. expansion rods to be placed on the Hy-Rib sheets at right angles to the ribs at 2' 0" centres and wired thereto at every sixth rib (1' 9" centres) with 17 gauge wire. Laps 12" minimum and staggered.
3. During concreting, the Hy-Rib sheets are to be well supported by means of temporary bearers spaced at intervals not greater than those given in the following table:

Gauge of Hy-Rib	Thickness of Concrete						
	3"	3½"	4"	4½"	5"	5½"	6"
26G.	2' 6"	2' 4"	2' 2"	2' 0"	1' 10"	1' 8"	1' 6"
28G.	2' 3"	2' 1"	1' 11"	1' 9"	1' 7"	1' 5"	1' 3"

The spacing must be reduced by 4" for every 1" thickness of wet concrete screed or finish placed in the same operation and which is extra to the thickness of concrete given in the span table above. The temporary bearers may be formed of rough timbers, tubular scaffolding or patent propping and after concreting these bearers must be left in position for the same length of time as would be necessary for a timber shuttered slab.



4. P.C. Concrete mix 1:2:4 throughout. The thicknesses of concrete shown in the span table above are minimum and concrete or screed for forming drainage falls or finishes must be additional.

FOR CONSTRUCTION DETAILS SEE DATA SHEET A

HY-RIB FOR FLAT CONCRETE ROOFS

THE TRUSSED CONCRETE STEEL CO., LTD.
TRUSCON HOUSE, LOWER MARSH, LONDON, S.E.1
Telephone: WATERloo 4922

Data Sheet B



CROSS SECTION

Hy-Rib is a combined centering and reinforcement and eliminates close board shuttering. The Hy-Rib mesh provides a ready-formed key for the plaster ceiling.

Notes on the construction of Hy-Rib roof slabs are given on Data sheet B with maximum spans for slabs of various thicknesses.

HY-RIB FOR FLAT CONCRETE ROOFS

THE TRUSSED CONCRETE STEEL CO., LTD.
TRUSCON HOUSE, LOWER MARSH, LONDON, S.E.1
Telephone: WATERloo 4922

Data Sheet A


THORNS STEEL PORTAL-FRAMED BUILDINGS

30' 40' 50' WIDE
10' 12' 14' 16' HIGH

Specify Thorns Portal-Framed structures for all kinds of one storey shedding. Frames only or sheeted buildings, with or without erection.

Also
Timber-framed buildings for Offices, Hospitals, Pavilions, Halls.

And
New Nissen type huts and "Blister" Hangars for many Industrial purposes.



**KEEP DOWN
COST AND
SPEED UP
ERECTION**



Write to:-

THORNS FOR FURTHER DETAILS

J. THORN & SONS LTD. (Dept. 183) BRAMPTON ROAD, BEXLEYHEATH, KENT. Tel. 305

BD647

**SINGLE OR MULTI-SPAN
UNOBSTRUCTED ROOF
SMALL FOUNDATIONS
SIMPLE TO ERECT
MANY STANDARD SIZES**



Werno is a wood framed unit with a filling of parallel straws, faced with selected sheet material. Panel frames are grooved to receive a wooden tongue which, with a special wedge system, ensures rapid erection. Specially trained labour is unnecessary, but we can erect it for you. Panels are available in many sizes, standards are 3ft., 3ft. 4in. and 4ft. wide up to 10ft. in height. Thickness dependent on finish, up to 2 1/2 in. Werno doors are constructed on the same principle and are available for polishing or painting.

THE ANSWER TO YOUR PARTITION PROBLEMS

- Each Werno panel is a structural wood framed unit.
- Can be faced with most sheet material, including ply veneers.
- No studs or framing required for erection.
- Joints can be secret or expressed.
- Easily cut on site or
- Factory cut to requirements.
- Wall fixtures easily mounted.
- Conduit and services can be run down, across or through the panels.
- Good sound absorption.
- Speedy and simple erection.
- Easily demountable for further uses.
- Highly adaptable to complex plans and elevations.

Made by:—Thames Plywood Manufacturers Ltd.

Under patents of A.B. WST-PATENTER, SWEDEN.

Write or telephone for information sheets to:

BRITISH WERNO LTD
77, PORTLAND PLACE, LONDON, W.1. LAngham 7702-3-4


TEMCO

A.C. SWITCH SOCKETS AND PLUGS

Right at every point!

QUALITY RIGHT

TEMCO A.C. Switch Sockets are small, attractive and individually packed. They conform to British Standards and I.E.E. Wiring Regulations.



WIRING RIGHT

Easy wiring is a notable feature of the new TEMCO A.C. Switch Sockets and Plugs. Heat Resistant Back Plates for the Surface Types are available to form an enclosure for the Cable Sheath.

PRICE RIGHT

You can confidently use TEMCO accessories even if low initial cost is important. Despite their high quality they are not expensive — proving that the best is really the cheapest.

Please write for our fully illustrated catalogue


Manufactured by

TELEPHONE MANUFACTURING CO. LTD.

and Marketed by their Sales Organisation:

T.M.C.-HARWELL (SALES) LTD


37 UPPER BERKELEY ST., LONDON, W.1 Tel.: PADdington 1867 9



WINDOGRID

CURTAIN WALLING AT PARLIAMENT HILL COUNTY
SECONDARY SCHOOL FOR THE L.C.C.

DOCTOR J. L. MARTIN, M.A., Ph.D., F.R.I.B.A., ARCHITECT TO THE COUNCIL



WINDOGRID with swing ventilators, metal window boards and blind boxes. Rough-cast glass at floor levels covers painted surfaces within. Panels covering stairs and cloakrooms are 'glazed' with mahogany veneer plywood, and fixed glass louvres inserted where required.

Send for List 295

HENRY HOPE & SONS LTD

Smethwick, Birmingham & 17 Berners St., London, W.1

MEMBER OF THE METAL



WINDOW ASSOCIATION



THE ARCHITECTS' JOURNAL

EDITORIAL BOARD: (1) *Consulting Editor*, F. R. Yerbury, O.B.E., Hon. A.R.I.B.A. (2) *House Editor*, J. M. Richards, A.R.I.B.A. (3) *Executive Editor*, D. A. C. A. Boyne. (4) *Editor Information Sheets*, Cotterell Butler, A.R.I.B.A. (5) *Editorial Director*, H. de C. Hastings.

GUEST EDITORS (Costs): (6) N. Stanley Farrow, M.B.E., M.I.O.B.; A. W. Cleeve Barr, A.R.I.B.A.; James Nisbet, A.R.I.C.S.; Ivan Tomlin, A.I.B.E.; E. F. L. Brech, B.A. B.Sc.(ECON.), M.I.I.A.

TECHNICAL EDITOR: (7) Lance Wright, A.R.I.B.A.

SPECIALIST EDITORS*: (8) Planning (9) Practice (10) Surveying and Specification (11) Materials (12) General Construction (13) Structural Engineering (14) Sound Insulation and Acoustics (15) Heating and Ventilation (16) Lighting (17) Sanitation (18) Legal.

ASSISTANT EDITORS: (19) *Chief Assistant Editor*, Kenneth J. Robinson. (20) *Assistant Editor (Buildings)*, L. F. R. Jones. (21) *Assistant Editor (Production)*, W. Slack. (22) *Assistant Editor (Information Sheets)*, V. A. Groom. (23) *Assistant Editor (Costs)*, J. Carter, A.R.I.B.A. (24) *Photographic Department*, H. de Burgh Galwey, W. J. Toomey. (25) *Editorial Secretary*, Monica Craig.

* To preserve freedom of criticism these editors, as leaders in their respective fields, remain anonymous

9, 11 & 13 Queen Anne's Gate, Westminster, London, S.W.1 Whitehall 0611

No. 3184/5 March 8 & 15, 1956 VOL. 123

Subscription rates: by post in the U.K. or abroad, £2 10s. 0d. per annum. Single copies, 1s.; post free, 1s. 3d. Special numbers are included in Subscriptions; single copies, 2s.; post free, 2s. 3d. Back numbers more than 12 months old (when available), double price. Half-yearly volumes can be bound complete with index in cloth cases for 30s.; carriage, 1s. extra.



A CINERAMIC SURVEY

Fame at last! ASTRAGAL has achieved the improbable honour of being mentioned in a *General History of Architecture*. The honour is due to the industrious, erudite and highly controversial Bruce Allsopp, of the University of Durham, whose new book, coming on top of the grand overhaul of Simpson now in progress, and Hugh Braun's *Historical Architecture* of a couple of years back, seems to suggest that great Cineramic surveys of the architectural past are the order of the day.

*

ASTRAGAL is not really sufficient of a historical expert to justify inclusion in such a work, and modestly has no intention of trying to assess its overall

value, but there looks like being some lively skirmishing around some of the opinions with which Mr. Allsopp has diversified his text. Supporters of Mackintosh and Victor Horta will surely have a few things to say about the statement that Art Nouveau was "constructionally unsound," several people will have quite a lot to say about his opinion of the Baroque—"... a sterile movement, or at least it could bring forth nothing but monstrosities"; of the High Renaissance "... restrained to the point of dullness"; that Lutyens was better than Voysey; that for architects the dissolution of the monasteries "must have been a very distressing event"—surely the nearest things to architects in the middle fifteen-hundreds were to be found in the Thorpe and Smythson families, who appear to have done rather well out of the monastic loot.

*

*



Mr. Allsopp has every right—and ASTRAGAL'S encouragement—to dissent from fashionably-held opinion, but his grounds must be relative to the ascertainable facts, proportionately deployed. And one cannot help wondering about his sense of proportion when in his chapter on the architectural revolution of our own times he does not even mention Gropius and appears to consider Erich Mendelsohn more worthy of illustration than Le Corbusier. At this ASTRAGAL, notoriously a slave to the fashionably unfashionable, boggled.

FILM AS AN OUTRAGE WEAPON



Those who have an institution or a service to sell to the public—civic design, say, or the architect in house-building—are apt *not* to think of a

two-reel colour film as a way of selling it. We have seen too many dreary shorts exhorting us to do this, stop that, admire the other. But the trouble doesn't necessarily lie with the short film as such—and ASTRAGAL feels particularly strongly about this after seeing *Man of Action*, a short intended to stir up citizen feeling against urban squalor. (ACTION is the American Council to Improve Our Neighbourhoods.) Although this film was made specifically for American consumption, about a specifically American problem, and will never, presumably, have a normal screening over here, bodies like the CPRE, the proposed Council of Civic Design, the Public Relations Committee of RIBA, Outrage-fighters and so forth, should at least try to organize some limited showings for interested bodies.

Man of Action is a marvellous example of how to sell a serious theme without being dreary about it, the rather high-toned commentary being nicely balanced against a beautifully-drawn animated fable of urban rehabilitation, and a witty, pretty and highly hummable musical score. To bone-head groaners who will want to reply that we don't have these brilliant American Public-Relations men over here, and, in any case, the cost... there is one simple reply. ASTRAGAL was only able to see this film because it was made in England, with English technicians and musicians, designers and animators. Made here because ACTION is, like all bodies of its kind, not very affluent and work of this kind costs half as much here as in the States. Now get in there, do-gooders!





LONDON OF THE FUTURE ON VIEW
AT THE BUILDING CENTRE



Top, left and right, offices by Guy Morgan and Partners for a site in Knightsbridge opposite the top of Sloane Street. Above, offices in New Cavendish Street by Gollins, Melvin, Ward & Partners. Left and below left, model and plan of the proposals, proposed jointly by the LCC and the City Corporation, for the Barbican area. Note the extensive basement car parks and high-level pedestrian ways. Below, the Kingswood Drive Secondary School, Alveyn Park, Dulwich, by Dr J. L. Morgan.

Note the extensive basement car parks and high-level pedestrian ways. Below, the Kingswood Drive Secondary School, Altem Park, Dulwich, by Dr J. L.



PUGIN REVISITED

More concerned with Lord Shrewsbury and Bishop Milner than its ostensible subject, Pugin, the lecture by T. S. R. Boase, the president of Magdalen College, given recently at the Courtauld Institute, struck ASTRAGAL as particularly interesting for the way in which it played up the influence of internal Catholic squabbles on Pugin's development. Histories of early Victorian Gothic tend to have a lot to say about ecclesiology and the Anglican's Camden Society, but very little about the equivalent disputes and polemics inside Catholicism—the attempt by Pugin, Ambrose Phillips and others to get rid of “Hired sopranos and protestant fiddlers,” and other “Italianisms,” and to reintroduce Sarum Use, Choir screens, the full English Surplice, plain-song, and so forth.

*

Brompton Oratory was the tombstone of all these hopes, and it was probably just as well that Pugin was safely dead by the time it was completed. Even before 1850 Pugin was ruefully observing that the Camden wing of the Anglican Clergy were more receptive to his ideas than was his own persuasion, and it was in the Church of England that his ideas were posthumously to find their fullest expression.

*




Moral for all Reformers—you can't win. Footnote, for amateurs of Victorian opinion at its craziest. Prof. Boase quoted an un-named ecclesiologist for the dictum that, though Middle Pointed was the only true Christian style in architecture, Romanesque “might suit in New Zealand.”

ASTRAGAL


We very much regret that, in common with many other periodicals the Journal is prevented by the printers' dispute from appearing in its normal size and on the customary publishing date. Periodicals printed in the country are able to appear normally, but it is probable that the Journal, which is printed in London, will be unable to publish any normal issues until the dispute ends or circumstances change.

WINNING DESIGN FOR KAMPALA COMPETITION


This is the design for a legislative council building in Kampala, Uganda, which won Edward D. Mills & Partners the first prize of £750 in a competition assessed by H. Thornley Dyer. Other prizewinners' names were published in our last issue.




SOUTH-EAST ELEVATION



LONG SECTION THREE CHAMBERS




THREE OFFICES LOOKING SOUTHWEST




HANLOW ROAD

WEST FASDOR SECTION



SOUTH-WEST ELEVATION



C

Why is it that much of the best housing in this country is put up with little thought for the creation of an attractive environment? Ian. C. McHarg believes that it is due to fear of costs—a fear based on ignorance rather than knowledge. In this article he examines costs for the landscaping of five well-designed housing estates. If

these costs support the fears of developers, then—in Mr. McHarg's words—"we must consign present and future housing to permanent aridity" and resign ourselves to never achieving even the standards of, for example, the Swedes at Grondal, Stockholm, opposite page, and other enterprising European countries, as shown below.

A SURVEY OF LANDSCAPING COSTS

CAN WE AFFORD OPEN SPACE?

By Ian C. McHarg

Examples of housing in Denmark and Sweden, Switzerland and the Netherlands have elicited a widespread and deserved acclaim; yet all too often this appreciation fails to distinguish that the merit of such housing lies less in the buildings as exercises in architecture than in the quality of the total environment created. In these much admired North European projects, it is the unity of open space and building with the development of open space as an integral element of the environment which is the key to their distinction.

In terms of internal space standards, British municipal housing is without peer, in terms of design it is not remarkably below prevailing North European standards, but when the quality of the total housing environment is examined, it is obvious that British practice falls far below the standards of Scandinavia, Switzerland and Holland.

This invidious disparity is directly attributable to the general failure of British site planning but even more particularly to that failure to recognize the vital role of open space in housing. In the Swedish estates of Grondal, Friluftstaden, and in the Dutch Frankendaal, it is the site plan and the development of open space which explains the distinction of these projects; there the development of the landscape is an integral element in the design of the project. This is in direct contrast to the majority of British practice in which the development of open space is conceived as an additive function. Open space is conceived as a residue and as such its development can be omitted—ostensibly on grounds of cost.

Yet this attitude is contrary to the best British traditions of housing. The history of housing reform during the past century has been mainly a movement to improve standards of open space. That housing which has brought prestige to British architecture—the 18th and 19th century residential squares of London, Bath and Edinburgh—is remarkable for both the provision of open space and the quality of its design. The Garden City Movement, however regarded today, represented the peak of British influence in the field of housing; here, too, the distinction lay, not in the architecture, but rather in the quality of the environment created.

Welwyn and Letchworth are distinguished by the provision, organization and design of open space which has now realized a lush, foliate landscape and a humane



In the Grondal, top, Friluftstaden, centre and Frankendaal estates, it is the site plan and the development of open space rather than the buildings as exercises in architecture which explains their distinction.

environment. Yet the mass of British municipal housing fails to attain either the urbanity and humanity of the 18th and 19th residential squares or the leafy romanticism of the Garden Cities.

While the Scandinavian designers interject buildings into the natural landscape and achieve a dramatic unity of site and structure, in Britain the *genius loci* is usually erased and a monotonous stencil of houses superimposed on the landscape. In the Netherlands, where the site seldom contains any distinguishing features, the conscious development of open space in housing creates an attractive total environment. In similar British situations, too often the environment consists of a dreary pattern of houses aligning the street.

Traditionally, the reform movements in British housing have been concerned with the provision of open space. That housing which has brought prestige to British architecture shows an emphasis upon the organization and design of outdoor space. The much admired foreign projects are distinguished mainly for the integration of open space and housing to create a dramatic unity of space and structure. In the face of these successes depending upon the development of open space, it is difficult to understand the chronic disinterest in the design of open space which has characterized the bulk of British housing for the past thirty years.

I submit that one reason for the disinterest is that municipal housing has never overcome its charity origins and it still carries the stigmata of subsidized housing. And, although hardly a major reason, it is surely contributory that those persons involved in the process of municipal housing—central and local government officials, architects, engineers and planners—seldom live in council houses. However, the one overwhelming reason for indifference to the development of open space in housing is the fear of costs. Local and central government officials are fearful of the capital cost of development, they balk at the recurring cost of maintenance, and they have no solutions for the social problem of allocating responsibility for open space or the economic problem of maintenance. This attitude did not halt the creation of the 18th and 19th century residential squares, it did not obstruct the struggling, unsubsidized Garden Cities, it does not affect the design of excellent housing elsewhere in North Europe or in certain New Towns. There is, therefore, reason to doubt its applicability to the British situation. Indeed, I will say more, this attitude to cost is based on apprehension and ignorance rather than upon any precise knowledge of the actual costs involved.

This fear of costs has had many repercussions, it has bequeathed the nation a legacy of arid, ugly and socially unsatisfactory housing. The aridity stems simply from the lack of landscape treatment, but this is the most superficial weakness. The attitude to open space which avoids its development also inhibits innovations to the site plan. The cul-de-sac, green, single footpath access, double footpath access, service cul-de-sac, European and American internal courts—each of these site plan types requires the provision of a certain proportion of common open space to be designed, constructed and maintained by the housing authority. Such site plans

represent improvements over the British Municipal Convention, but they tend to be rejected on the grounds of cost, supported by claims that landscape treatment is prohibitively expensive, or, in the case of common open space, that not only is such space wasteful and expensive to develop, but the associated social and administrative problems of vandalism, maintenance, and responsibility are insuperable.

It is important to determine if this prevalent and negative attitude is supported by objective evidence. The quality of British housing can be improved in many ways, improving the quality of environment by the development of open space is one of the most important. Objective information on the capital and maintenance costs of open space development can permit a more flexible attitude to new site-plan types, it can permit the organization of society in open space so as to intensify the sense of community, to satisfy the functions of active and passive recreation, to provide shade and shelter and to add grace to the residential environment.

If current prejudices and fears are supported by objective evidence on costs, then we must consign present and future housing to permanent aridity. If, in contrast, it is found that a wide range of open-space development costs only insignificant sums then the invidious comparisons with housing in Scandinavia, Switzerland and the Netherlands need not persist and we can return to our valid tradition in both urban and rural situations.

Landscape Test Plans

In order to obtain precise information on the capital and maintenance costs of open space development the technique used was to prepare a number of test plans, accompany each with a bill of quantities and despatch them to competent agencies—superintendents of the major municipal park systems, landscape contractors, New Town Landscape Architects—with the request that each bill of quantities be costed and an estimate of annual maintenance cost made for each plan.

The function of these plans was to obtain information on costs, not to demonstrate methods of developing open space. The assumption is that, given information as to costs, one designer can dispose a given quantity of materials to little effect, another designer can, with the same quantity of materials, significantly enhance the environment. The prime function of the test plans was to provide information on costs from which decisions on policy could be made and to demonstrate the relationship of certain types of open space development to unit area costs. Consequently, the test plans incorporate extant types of development and conventional plant materials.

The first test plan exemplifies typical two-storey municipal housing at 12 families to the acre. In this example only street planting, verge planting and non-apportioned corner interstices are planted and maintained by the municipality. This form is implicit in the bulk of municipal housing but seldom is the planting and maintenance realized.

Plan number two is identical with the first save that all open space between the house and the street is planted and maintained by the municipality. This form is meet



"Capital costs to meet the standards of test plan 1, including the development of all open space between house and street can be achieved at a cost of 3d. in England and 2½d. in Scotland per house per week."



"Capital costs to meet the standards of test plan 2 including development of all open space between house and street can be achieved at a cost of 4d. in England and 2¾d. in Scotland per house per week."



"Standards of test plan 4, with open space developed between house and street in four storey construction can be met at costs of 1d. per house per week in both England and Scotland."

ing widening acceptance and is the norm for New Towns.

The third test plan varies from those preceding in several ways. Although an example of two-storey housing, its organization of open space is radically different from the previous examples. Epitomized in the Frankendaal, Amsterdam, by Merkelbach and Elling, all houses back to the street, face first on to small private open space; there is no common usable open space. Houses are disposed in two "L" shaped terraces, one of which is an inverted "L." Each common space enclosed by these terraces is 250 ft. by 140 ft. and contains a tot-lot and an adult conversation area to serve the abutting 36 families. All space, save private gardens, is designed as public open space and is planted and maintained by the housing authority. The density is 17 families to the acre.

Test plan number four is an example of typical uniform four-storey development in which flats face the street, the open space between house and street being ostensibly the responsibility of the municipality, while open space to the rear is consigned to a forest of drying green poles as private open space. The density is 28 families to the acre.

The final plan is a further example from Holland. Epitomized by the Klienpolder, Rotterdam, it consists of uniform four-storey development with flats backing upon the street, the open space extending from living rooms treated as common open space, incorporating children's play areas, adult seating areas, with all open space planted and maintained by the municipality. The density is 55 families to the acre.

In these plans there are two distinct qualities of landscape treatment; plans 1, 2, and 4 are typical of conventional British development in which either the majority or a large proportion of open space is private open space; there is no common usable open space, there are no communal facilities and planting is only decorative. In contrast, in plans 3 and 5, the majority of all open space is common, there are communal facilities—tot-lots, conversation areas—and both the organization of open space and its treatment are functional rather than merely decorative. Additionally, in these latter examples the provision of both inert and plant materials is more lavish than in the other test plans. The "Landscape Costs" exclude the cost of land, the labour of bringing the site to final line and grade, and the cost of paths, but do include all treatment of common open space. In this category fall the costs of tilling and sowing, all plant materials—trees, shrubs, hedges, herbaceous, grass seed, stakes and their planting costs, all paving—sand boxes, sand, cost and labour, plus a contingency allowance for all costs, varying from 5 per cent. to 20 per cent.

The bills of quantities were costed and estimates for annual maintenance calculated by Directors of the Municipal Park Systems of London, Glasgow, Southampton, Edinburgh, Coventry, by the Landscape Architects in the New Towns of Harlow, Hemel Hempstead, Stevenage, Welwyn, East Kilbride and Glenrothes and by two landscape contractors, Maxwell M. Hart and Waterer, Sons and Crisp. The figures presented are averages obtained from these sources.

The survey, from which this article was developed, was conducted by the author when an official of the Department of Health for Scotland to ascertain objective information on the costs of development and maintenance of open space in housing.

Financial and administrative technique

There are certain financial and administrative techniques which are indispensable to the general acceptance and success of open space development in municipal housing. The first of these is the "Landscape Rent." This technique consists of meeting the capital cost of open space development with a 60-year loan at 4½ per cent. as is usual in housing finance, meeting the recurring cost of maintenance with equity capital from a floating fund and retiring both costs by equal payments per house per week as landscape rent. This technique spreads the capital cost over the life of the house. The mortgage payments are made in equal weekly sums which offers the advantages of mortgage financing, common in housing, to the development of open space. The establishment of a landscape rent can reflect the ability of the tenant to pay, it creates a reciprocal client-entrepreneur relationship between tenant and housing authority, which, apart from its obvious merit, should militate against vandalism. The final advantage results from the separation of open space development from structure and service costs. Normally where a total sum is made available for land, house, utilities and open space, the latter is the inevitable victim of the inevitable economies. The landscape rent separates open space development into an independent account in which capital and maintenance expenditures are balanced by revenue from weekly landscape rents.

In addition, in the context of this article, the Landscape Rent offers an excellent means of evaluating the capital and maintenance costs of open space development in relation to ordinary shelter rent.

This technique does not lack precedents. In the residential squares of London, Edinburgh, and in the Garden Cities, it has long been usual to levy a charge upon tenants for the maintenance of open space in


joint ownership. In Hemel Hempstead a sum of £12 approximately is allocated to the capital cost of landscape treatment per house and a charge of 9d. per house per week is levied for maintenance. But it is in the Netherlands that this technique is most widely practised. Originating in the post-war period, it has spread into general use for all municipal housing.

Vandalism is a vital consideration in this contest. As has been suggested, the payment of a landscape rent should tend to defer tenants from either practising or condoning vandalism. This is not enough. In typical municipal development it is difficult to induce a sense of responsibility in tenants for specific areas of open space. Yet, perhaps the most efficacious technique for reducing vandalism is to allocate specific areas of open space to the responsibility of abutting tenants.

This method, combined with the landscape rent, must induce both an individual and collective sense of responsibility militating against vandalism. The technique of allocating responsibility to tenants for specific areas of open space presents no problems in the internal court site plans. All abutting tenants are responsible for the enclosed, common open space. In the internal court project, the Frankendaal in Amsterdam, there are further administrative techniques, designed to discourage vandalism. In each lease, tenancy is conditional upon agreement that common open space is the collective responsibility of all abutting tenants; that damage will be made good by equal fines imposed upon all abutting tenants; and finally that failure to pay any fine, so imposed, will result in summary eviction. This project is high subsidy housing for a working class population; initially there were cases of vandalism; damage was made good and the lease conditions imposed. In the subsequent three years there has been no single recurrence of vandalism. Each of these techniques—the landscape rent, the allocation of responsibility to tenants for specific areas of open space, the collective fine and powers of summary eviction—are important ingredients to the policy of introducing general landscape treatment to housing areas.


From these tables it is immediately apparent that when

2 two-storey development : orthodox site plan
municipal construction and maintenance of street front sites




16 houses

4 Four storey development : orthofax site plan
municipal construction and maintenance & street front sites



48 houses

LANDSCAPE TEST PLANS



80 houses'

Above and right are the five test plans referred to on page 262 and subsequently. Comparative data on the capital costs and development for these plans are given in the twelve tables on the next page and on page 267. The plans are reproduced again, accompanied by a landscape specification, with average costs, for English and Scottish local authorities, on pages 269-275.

THE COST OF OPEN SPACE DEVELOPMENT

(i) Capital Costs

TABLE 1: CAPITAL COSTS PER HOUSE PER WEEK

	England d.	Scotland d.
test plan 1	3	2½
test plan 2	4	2½
test plan 3	7½	4½
test plan 4	1	1
test plan 5	1½	1

TABLE 2: RELATION OF OPEN SPACE TO HOUSE CAPITAL COSTS

	England		Scotland	
	Open space £ s. d.	House, %	Open space £ s. d.	House, %
test plan 1	14 1 4	1,500 0.91	11 11 6	1,500 0.77
test plan 2	21 2 0	1,500 1.40	12 14 7	1,500 0.85
test plan 3	34 0 0	1,500 2.26	20 16 8	1,500 1.39
test plan 4	4 13 10	2,000 0.23	4 12 7	2,000 0.31
test plan 5	7 0 8	2,000 0.35	4 12 7	2,000 0.31

TABLE 3: CAPITAL COSTS AND DEVELOPED AREA PER HOUSE

	Development area/house	Capital costs, house/week	
		England d.	Scotland d.
test plan 4	410 sq. ft.	1	1
test plan 5	450 sq. ft.	1½	1
test plan 1	1,067 sq. ft.	3	2½
test plan 3	1,156 sq. ft.	7½	4½
test plan 2	1,525 sq. ft.	4	2½

TABLE 4: CAPITAL COST OF DEVELOPED OPEN SPACE PER ACRE

	Dev. Open Space/Acre	Capital Cost of Dev. Open Space/Acre	
		England £ s. d.	Scotland £ s. d.
test plan 1	11,700 sq. ft.	150 0 0	105 16 0
test plan 2	16,718 "	198 0 0	138 8 0
test plan 3	19,560 "	565 5 0	365 10 0
test plan 4	12,716 "	148 0 0	105 12 0
test plan 5	22,800 "	371 3 6	255 8 0

TABLE 5: CAPITAL COSTS AND DEVELOPED AREA PER HOUSE

	Test Plan	Dev. Area/House	Capital Costs House/Week	
			England	Scotland
conventional development	{ 4	450 sq. ft.	1	1
	{ 1	1,067 "	3	2½
	{ 2	1,525 "	4	2½
Kleinpolder-Frankendaal development	{ 5	410 "	1½	1
	{ 3	1,156 "	7½	4½

TABLE 6: CAPITAL COST OF DEVELOPED OPEN SPACE

	Test Plan	Dev. Open Space/Acre	Capital Cost of Dev. Open Space/Acre	
			England £ s. d.	Scotland £ s. d.
conventional development	{ 4	12,716 sq. ft.	148 0 0	105 12 0
	{ 1	11,700 "	150 0 0	105 16 0
	{ 2	16,718 "	198 0 0	138 8 0
Kleinpolder-Frankendaal development	{ 5	22,800 "	371 3 6	255 8 0
	{ 3	19,560 "	565 5 0	365 10 0

TABLE 7: THE RELATIONSHIP OF CAPITAL COSTS TO DENSITY

	Test Plan	Density	Capital Costs	
			England d.	Scotland d.
conventional development	{ 4	28	1	1
	{ 2	12	4	2½
Kleinpolder-Frankendaal development	{ 5	55	1½	1
	{ 3	17	7½	4½

(ii) Maintenance Costs

TABLE 8:

	Maintenance Cost per House per Week	
	England s. d.	Scotland s. d.
test plan 1	1 1	9½
test plan 2	1 5½	1 1½
test plan 3	1 5½	10
test plan 4	6½	5
test plan 5	5	4

TABLE 9: THE RELATIONSHIP OF CAPITAL TO MAINTENANCE COSTS

	England Capital Costs House/Week d.	Per cent.	Scotland Maintenance Costs House/Week s. d.
test plan 1	3	23	1 1
test plan 2	4½	25	1 1½
test plan 3	7½	42	1 5½
test plan 4	1	15	6½
test plan 5	1½	30	5
Scotland			
test plan 1	2½	27	9½
test plan 2	2½	20	1/1½
test plan 3	4½	45	10
test plan 4	1	20	5
test plan 5	1	25	4

capital costs are financed by equal weekly payments over the life of the house, with a 60-year mortgage at 4½ per cent., these weekly payments, even for the most lavish standards of development, are within the capacity of a widow's pension or income from National Assistance. It is a tragedy that sums of such insignificance have obtruded between the typical sterility of the past 30 years of municipal housing and the more humane environment realizable for such puny expenditures. These costs vary between 0.05 per cent. and 0.225 per cent. of the average national weekly income (Scotland 1954). If maintenance is not considered, if it is assumed that tenants can carry out maintenance either privately or by voluntary co-operation, then the capital cost of open-space development, even of the most lavish scale, offers no obstruction to its realization.

Tables 1 and 2 show that while the test plans incorporate a range of treatment from marginal to lavish, there is no corresponding range of costs at this low scale between the extremes of 1d. and 7d. per house per week.

No worthwhile economies can be achieved in this sector of capital costs. It is rather in an appreciation of the components of maintenance costs and the relation of density to all costs which offers opportunity for achieving economies.

While recognizing that capital costs are insignificant sums in terms of rent per house per week, there are nevertheless certain inferences to be drawn from them. The first point is to appreciate the qualitative difference in these various test plans. As can be seen from tables 4 and 5, plans 1, 2 and 4 represent a distinctly lower standard of open space, this provision and development is indicated by both the area and the cost of developed open space per acre. From these tables we can see that capital costs, within any type of development, correspond closely to the area of developed open space.

This general correspondence between developed area and capital costs for distinct levels of development introduces the relationship of density to capital costs. As this correspondence would lead us to expect, we can assume that by raising the residential density the standard of open-space development can also be raised without any increase in capital costs per house. Inversely, we can say that, assuming a constant standard of landscape treatment, capital costs per house will fall as density is increased.

The relationship of residential density to capital cost is a striking one. Test plan 4 illustrates the minimum open-space provision and the lower standard of open-space development in four-storey construction. The relevant figures are 12,716 sq. ft. of developed open space per acre at a cost of £105/acre (Scotland) and £148/acre (England). Test plan 5 provides 22,800 sq. ft./acre at £255/acre (Scotland), £371/acre (England), which indicates a provision of open space and standard of development more than twice that of test plan 4. Yet the capital costs per house per week are identical for Scotland and similar for England. The key to this paradox lies in the relative densities, 28 and 55 families per acre respectively.

TABLE 10: THE RELATIONSHIP OF DEVELOPED AREA TO MAINTENANCE COST

	Dev. Open Space/House	Factor	Maintenance Costs House/Week England s. d.	House/Week Scotland s. d.
test plan 5	410 sq. ft.	4.1	5	4
test plan 4	450 "	4.5	6½	5
test plan 1	1,067 "	10.7	1 1	9½
test plan 3	1,156 "	11.6	1 5½	10
test plan 2	1,525 "	15.3	1 5½	1 1½

Table 10 demonstrates that maintenance costs correspond generally to units of area. The use of low maintenance materials—paving, ground covers, herbaceous—in plans 3 and 5—is also partially indicated by this table.

TABLE 11: THE RELATIONSHIP OF DENSITY TO MAINTENANCE COSTS

	Density	Maintenance Costs, House/Week England s. d.	House/Week Scotland s. d.
test plan 5	55 fam./acre	5	4
test plan 4	28 " "	6½	5
test plan 3	17 " "	1 5½	10
test plan 2	12 " "	1 5½	1 1½

(iii) Total Landscape Rents

TABLE 12:

	Capital Costs	England, House/Week Maintenance Costs s. d.	Landscape Rent s. d.
test plan 1	3	1 1	1 4
test plan 2	4	1 5½	1 9½
test plan 3	7½	1 5½	2 0½
test plan 4	1	6½	7½
test plan 5	1½	5	6½
	d.	s. d.	s. d.
test plan 1	2½	9½	11½
test plan 2	2½	1 1½	1 4½
test plan 3	4½	10	1 2½
test plan 4	1	5	6
test plan 5	1	4	5

This relationship can also be seen in examples of two-storey construction. Test plan 1 has a minimum provision and a standard of development of 11,700 sq. ft./acre at a cost of £105/acre (Scotland), £148/acre (England); test plan 3 incorporates twice this provision at three times the cost per acre—19,560 sq. ft. at £365/acre (Scotland) and £565/acre (England)—yet the respective capital costs are 2½d. and 4½d. per

house per week for Scotland, 3d. and 7½d. for England. The respective densities are 12 and 17 families to the acre.

There is, then, a straight line relation between provision and cost of development of open space and density. If we wish to ascertain the relationship of capital costs for two schemes at different densities and having distinct levels of open-space provision and cost of development, this can be obtained by establishing a factor for each from the following formula and relating them.

$$\frac{\text{standard of open space provision, sq. ft. per acre}}{\div \text{density}} = \frac{\text{cost of open space development per acre}}{\div \text{density}}$$

Thus the most important conclusions to be drawn from capital costs are that as weekly rents they are insignificant sums, that even the most prodigal development costs a paltry sum and offers no obstruction to its realization, that for any level of development, capital costs closely correspond to the units of area developed and, as a result, any predetermined level of open-space development can be realized at various capital costs, depending upon the residential density.

Traditionally, the design or planting of municipal house gardens has been based upon the attitude that capital costs—the purchase of trees, shrubs, hedges, herbaceous, annuals, grass seed, stakes, paving—represent a cash investment while the labour of continuous maintenance has no cash equivalent—it is leisure employment. While this is appropriate to private gardening, it is inappropriate to the situation where maintenance is done by the housing authority.

NOTE: The landscape test plans, with specifications and costs, which follow on page 269 and subsequently are not in numerical order, but in the order Plan 1, 2, 4, 3 and 5

Right: "Capital costs to realize the standards of the Frankendaal, test plan 3, can be met by capital costs of 7½d. per house per week in England, and 4½d. in Scotland".



Right: Closed communal garden, Schiedam. Above: Communal gardens, Kleinpolder, West Rotterdam. "Kleinpolder-type development, test plan 5, can be achieved at capital costs requiring payments of 1½d. per house in England and 1d. in Scotland."



In such a case the labour of maintenance is not a leisure occupation but employment with the same cash equivalent as capital investment. The attitude of the private gardener has been towards minimizing the capital investment with the effect of maximizing maintenance which has no apparent cost. In contrast where the same authority is responsible for both services, it is more economical to maximize capital investment with a view to minimizing the recurring cost of maintenance and the total investment.

Tables 8 and 9 show maintenance costs per house per week and the relation of capital costs to maintenance costs. It is seen that capital costs range from one fifth to a half of maintenance costs and average 25 per cent. It is obvious that it is the capital investment which determines the quality of the environment while maintenance only sustains that quality. Capital costs should logically be preponderant but in the British convention of open space development it is seen to be the contrary. In the case of the Frankendaal and Kleinpolder examples, however, it is shown that in both cases capital costs approach half the maintenance costs, twice as high a proportion as the average, but even these examples demonstrate an attitude to maintenance which is a residue from private gardening.

This attitude is particularly apparent in the use of lawn areas. Grass is the cheapest ground cover measured by capital cost alone but when the cost of maintenance is added it becomes almost as expensive as marble. Indeed it is the high recurring cost of maintaining grass which accounts for the greatest proportion of maintenance costs.

The average capital cost of tilling, sowing, seeding, rolling and purchase of grass seed disclosed by the survey was 1s. per sq. yd. The average cost of maintenance, involving mowing each two weeks, a total of 15 cuts during the season, was 7d. per sq. yd. When to this capital cost is added the recurring cost of maintenance over the 60-year life of the building, the total cost is 36s. per sq. yd.

By way of contrast the total cost of excavation, bottoming, providing and laying concrete slab paving averaged 16s. per sq. yd. with no significant future maintenance costs (in both categories 10 per cent. allowance for contingencies would cover repairs). Thus grass, as a surface, is over twice as expensive as pre-cast concrete slab paving when the cost of maintenance is evaluated.

It is not suggested that these materials are interchangeable. Nevertheless, such a comparison gives greater freedom to the designer. It also indicates that green ground covers other than grass should be sought. There are, of course, many ground covers which, while unable to tolerate wear as well as does grass, can provide a green, textured surface. Where wear is not a consideration, many ground covers are not merely substitutes but rather superior materials to grass. The most obvious ones are ivy in variety, pachysandra, adjuga, hypericum; each provides a textured green plane but requires low maintenance.

Maintenance costs, as has been shown, are multiples of capital costs; this is at once illogical and unnecessary.

It requires only an appreciation of the real expense of grass areas to substantiate the lack of logic; it requires only recognition of the economies realizable by the employment of ground covers and paving materials to prove the lack of necessity for this situation.

As we have seen, maintenance costs generally correspond to units of area, consequently with increased density, and a reduction of unit area per house, there is a corresponding reduction in maintenance costs. This holds true even when, as in a comparison of plans 2 and 3, the former provides only marginal development and the latter incorporates the highest standards. Yet the more lavish development is lower in cost; the respective densities are 12 and 17 families to the acre. As with capital costs, we can say that, assuming a constant standard of maintenance, costs per house will decrease as density is increased.

Capital and maintenance costs together provide the total landscape rents. Although the addition of maintenance has raised these sums beyond the initial insignificance of capital costs alone, it can be seen that they are still inconsiderable. Plan 5, which represents a standard of open space development, at its density, superior to the best British practice costs less than three cigarettes a week. Plan 3, irrespective of density, provides environment superior to any recent British project of municipal housing and costs the equivalent of ten cigarettes per week.

The inferences to be drawn from the total landscape rents closely correspond to those observed in the analysis of capital and maintenance costs. Total costs, as rents per house per week, are low. The range in quality of development does not show a corresponding range in costs. The difference between the environment and facilities offered by plans 1 and 3 is extremely wide, the difference in cost is a few pence per week. The relationship of density to cost is clearly reflected; plan 5 incorporates the higher standard of provision and development of open space in the four-storey examples but costs less than plan 4; plan 3, incorporating the highest standards of open space development in two-storey projects, is similar in cost to plan 2 which has a lower provision and quality of development.

These landscape rents do not support the widespread misapprehension and fear of the cost of open space development in housing, they are seen to be within the capacity of all but the most indigent, they do not offer any obstruction to the design of new and more satisfactory site plans incorporating common open spaces, or the employment of a wide range of plant and inert materials. I suggest that this information can be used to influence policy on the development of open space in housing, that it offers a new freedom to architects, landscape architects and planners. No longer can it be argued that the costs of open space development are such as to consign all past and future municipal housing to permanent aridity, or to inhibit the development of improved site plans. Accurate costs have been shown. The development of open space is cheap. Do the savings effected by omitting treatment justify the abject environment of typical municipal housing or the invidious comparisons with practice in Denmark, Sweden, Switzerland and the Netherlands?

In calculating landscape costs it is assumed that bringing the site to finished alignment and level- and spreading topsoil is a charge to housing. Landscape costs include any purchase of plant and inert materials, the labour cost of establishing them and the recurring cost of maintenance.

Landscape Specification			Average costs for English Municipal and New Town Corporations			Average Costs for Scottish Municipal and New Town Corporations		
Item	Number		Unit cost	Sub total	Total	Unit cost	Sub total	Total
			£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
1	6	Tilia euchlora, 10 ft.-12 ft.	1 0 0	6 0 0		16 0	4 16 0	
	1	Tilia petiolaris, 10 ft.-12 ft.	18 0	18 0		16 0	16 0	
	1	Tilia platyphyllos, 10 ft.-12 ft.	18 0	18 0		16 0	16 0	
	4	Betula verrucosa, 10 ft.-12 ft.	10 6	2 2 0		12 6	2 10 0	
	1	Betula Delavayi Forresterii, 10 ft.-12 ft.	1 10 0	1 10 0		17 6	17 6	
	3	Sorbus aucuparia, 10 ft.-12 ft.	15 0	2 5 0		13 6	2 0 6	
	1	Laburnum alpinum, 10 ft.-12 ft.	1 0 0	1 0 0		15 0	15 0	
	1	Prunus avium, 9 ft.-10 ft.	10 6	10 6		17 6	17 6	
	1	Pyrus malus, standard	15 0	15 0		17 6	17 6	
	1	Pyrus albo pleno, standard	15 0	15 0		17 6	17 6	
	20	Stakes, felt and clout tacks	3 0	3 0 0		1 9	15 0	
		Labour cost of planting trees	—	7 19 0		8 0	8 0 0	
				27 12 6	27 12 6		24 16 0	24 16 0
2	225	Mixed shrubs of undernoted species and varieties: Cornus alba Kerria japonica Cornus mas Mahonia aquifolium Crataegus monogyna Pieris floribunda Crataegus oxyacanthioides Pieris japonica Cytisus albus Rhus typhina Cytisus praecox Rosa canina Andersonii Forsythia spectabilis Spartium Junceum Forsythia suspensa Syringa vulgaris atrocaulis Kalmia latifolia Ulex europaeus plenus Labour cost of planting shrubs	3 6	39 7 6		4 6	50 12 6	
				16 17 6		9	8 11 2	
				56 5 0	56 5 0		59 3 8	59 3 8
3		Grass seed for 1,500 sq. yds. tilling, sowing and rolling, 1,500 sq. yds.	1 6			2½ 11	15 12 6 68 15 0	
				112 10 0	112 10 0		84 7 6	84 7 6
4		Contingencies (England 20%, Scotland 10%). for replacement of trees for replacement of shrubs for resowing grass for additional topsoil		5 18 9 11 5 0 5 12 0	5 18 9 11 5 0 5 12 0		2 9 9 5 18 4 8 8 9	2 9 9 5 18 4 8 8 9
		Total Capital Cost			219 3 3			185 4 0
5		Estimated cost of annual maintenance			44 15 6			32 1 4

Landscape Rent per House per Week

	£ s. d.
Capital cost for 16 houses	219 3 3
Capital cost per house	13 13 11½
Assuming loan with 60-year amortization at 4½ per cent. interest: half yearly payments = £13.698 × 0.0231 = £0.316 weekly payments = £0.316 ÷ 26 = 3d.	
Thus capital costs can be retired by a weekly payment per house of 3d.	
Maintenance cost, per annum for 16 houses	= 44 15 6
Maintenance cost per annum per house	= 2 15 1½
Maintenance cost per house per week	= 1 1
Capital cost = 3d. Maintenance cost = 1s. 1d.	


Landscape Rent .. 1s. 4d. per house per week.

Landscape Rent per House per Week

	£ s. d.
Capital cost for 16 houses	185 4 0
Capital cost per house	11 11 6
Assuming loan with 60-year amortization at 4½ per cent. interest: half yearly payments = £11.575 × 0.0231 = £0.2673 weekly payments = £0.2673 ÷ 26 = £0.0102	
Thus capital costs can be retired by a weekly payment per house of 2½d.	
Maintenance cost per annum for 16 houses	= 32 1 4
Maintenance cost per annum per house	= 2 0 1
Maintenance cost per house per week	= 9½
Capital cost = 2½d. Maintenance cost = 9½d.	

Landscape Rent = 11½d. per house per week.

160-stone development: orthodox site plan
municipal construction and maintenance of cover sites and verges




16 HOUSES

landscape test plan

1

Landscape specification			Average costs for English Municipal and New Town Corporations			Average costs for Scottish Municipal and New Town Corporations		
Item	Number		Unit cost	Sub total	Total	Unit cost	Sub total	Total
			£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
1	6	Tilia euchlora, 10 ft.-12 ft.	1 0 0	6 0 0		16 0	4 16 0	
	1	Tilia petiolaris, 10 ft.-12 ft.	18 0	18 0		16 0	16 0	
	1	Tilia platyphyllos, 10 ft.-12 ft.	18 0	18 0		16 0	16 0	
	4	Betula verrucosa, 10 ft.-12 ft.	10 6	2 2 0		12 6	2 10 0	
	1	Betula Delavayi Forrestii, 10 ft.-12 ft.	1 10 0	1 10 0		17 6	17 6	
	3	Sorbus aucuparia, 10 ft.-12 ft.	15 0	2 5 0		13 6	2 0 6	
	1	Laburnum alpinum, 10 ft.-12 ft.	1 0 0	1 0 0		15 0	15 0	
	2	Prunus avium, 9 ft.-10 ft.	10 6	1 1 0		15 0	1 10 0	
	1	Pyrus malus, standard	15 0	15 0		17 6	17 6	
	1	Pyrus albo pleno, standard	15 0	15 0		17 6	17 6	
	21	Stakes, felt and clout tacks	3 0	3 3 0		1 9	1 16 9	
		Labour cost of planting trees		8 8 0		7 6	7 17 6	
				28 15 0	28 15 0		25 10 3	25 10 3
2	325	Mixed shrubs of undernoted species and varieties:— Cornus alba Kerria japonica Cornus mas Mahonia aquifolium Crataegus monogyna Pieris floribunda Crataegus oxycanthoides Pieris japonica Cytisus albus Rhus typhina Cytisus praecox Rosa canina Andersonii Forsythia spectabilis Spartium Junceum Forsythia suspensa Syringa vulgaris atrocaulis Kalmia latifolia Ulex europaeus plenus Labour cost of planting shrubs	3 3	52 16 3		4 6	73 3 6	
				24 7 6		6	8 2 6	
				77 3 9	77 3 9		81 6 0	81 6 0
3		Grass seed for 2,075 sq. yds. Tilling, sowing and rolling, 2,075 sq. yds.	1 6			2½ 7½	21 12 3 65 10 0	
				155 12 6	155 12 6		87 3 3	87 3 3
4		Contingencies (England 20%, Scotland 5%) for replacement of trees for replacement of shrubs for resowing grass, 5 per cent. for additional topsoil		5 15 0 10 11 3 7 15 6	5 15 0 10 11 3 7 15 6		1 5 6 4 1 3 4 7 1	1 5 6 4 1 3 4 7 1
		Total capital cost			285 13 0			203 13 4
5		Estimated cost of annual maintenance			60 8 2			46 16 0

two-storey development: preliminary site plan
municipal construction and maintenance of street front sites



Landscape Rent per House per Week

	£ s. d.
Capital cost for 16 houses	285 13 0
Capital cost per house	17 17 0
Assuming loan with 60 year amortization at 4½ per cent. interest	
half yearly payments = £0.411	
weekly payments = 4d.	
Thus capital costs can be retired by weekly payment per house of 4d.	
Maintenance cost per annum for 16 houses	= 60 8 2
Maintenance cost per annum per house	= 3 15 6
Maintenance cost per house per week	= 1 5½
Capital cost = 4d.	
Maintenance cost = 1s. 5½d.	
Landscape rent = 1s. 9½d. per house per week	

	£ s. d.
Capital cost for 16 houses	= 203 13 4
Capital cost per house	= 12 14 7
Assuming loan with 60 year amortization at 4½ per cent. interest	
half yearly payments = £12.729	
× 0.0231 = £0.2940	
weekly payments = £0.2940 ÷ 26 = 2½d.	
Thus capital costs can be retired by weekly payment per house of 2½d.	
Maintenance cost per annum for 16 houses	= 46 16 0
Maintenance cost per annum per house	= 2 18 6
Maintenance cost per house per week	= 1 1½
Capital cost = 2½d.	
Maintenance cost = 1s. 1½d.	
Landscape rent = 1s. 4½d. per house per week	

landscape test plan

2

Landscape specification			Average costs for English Municipal and New Town Corporations			Average costs for Scottish Municipal and New Town Corporations		
Item	Number		Unit cost	Sub total	Total	Unit cost	Sub total	Total
			£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
1	4	Tilia euchlora, 10-12 ft.	1 0 0	4 0 0		16 0	3 4 0	
	1	Tilia petiolaris, 10-12 ft.	18 0	18 0		16 0	16 0	
	1	Tilia platyphyllos, 10-12 ft.	18 0	18 0		16 0	16 0	
	2	Betula verrucosa, 10-12 ft.	10 6	1 1 0		12 6	1 5 0	
	1	Sorbus aucuparia, 10-12 ft.	15 0	15 0		13 6	13 6	
	1	Laburnum alpinum, 10-12 ft.	1 0 0	1 0 0		15 0	15 0	
	1	Prunus avium, 9-10 ft.	10 6	10 6		15 0	15 0	
	11	Stakes, felt and clout tacks	3 0	1 13 0		1 9	19 3	
		Labour cost of planting trees		4 8 0	15 2 6	7 6	4 2 6	
							13 6 3	13 6 3
2	300	Mixed shrubs of undernoted species and varieties:	3 6	52 10 0		4 9	71 5 0	
		Cornus alba Kerria japonica						
		Cornus mas Mahonia aquifolium						
		Crataegus monogyna Pieris floribunda						
		Crataegus oxycanthoides Pieris japonica						
		Cytisus albus Rhus typhina						
		Cytisus praecox Rosa canina Andersonii						
		Forsythia spectabilis Spartium Junceum						
		Forsythia suspensa Syringa vulgaris						
		atrocaulis						
		Kalmia latifolia Ulex europaeus plenus		22 10 0			10 5 0	
		Labour cost of planting shrubs						
				75 0 0	75 0 0		81 10 0	81 10 0
3		Grass seed for 1,800 sq. yds.	1 6			2½	18 15 0	
		Tilling, sowing and rolling 1,800 sq. yds.		135 0 0	135 0 0	11	82 10 0	
							101 5 0	101 5 0
4		Contingencies (England 20% Scotland 10% average, for replacement of trees for replacement of shrubs for resowing grass 5 per cent. for additional topsoil		3 0 10 15 0 0 6 0 9	3 0 10 15 0 0 6 0 9		26 12 9	26 12 9
		Total Capital Cost			249 4 1			222 4 0
5		Estimated cost of annual maintenance			69 6 6			52 0 0


Landscape Rent per House per Week

	£ s. d.
Capital cost for 48 houses	249 4 1
Capital cost per house	5 3 10
Assuming loan with 60 year amortization at 4½ per cent. interest	
half yearly payments = £5.191	
weekly payments = £0.0045 = 1d.	
Thus capital costs can be retired by weekly payment per house of 1d.	
Maintenance cost per annum for 48 houses	= 69 6 6
Maintenance cost per annum per house	= 1 8 1½
Maintenance cost per house per week	= 6½
Capital cost = 1d.	
Maintenance cost = 6½d.	
Landscape Rent = 2s. 7½d. per house per week	

Landscape Rent per House per Week

	£ s. d.
Capital cost for 48 houses	222 4 0
Capital cost per house	4 12 7
Assuming loan with 60 year amortization at 4½ per cent. interest:	
half yearly payments = £4.629	
× 0.0231 = £0.1069	
weekly payments = £0.1069 ÷ 26 = 1d.	
Thus capital costs can be retired by weekly payment per house of 1d.	
Maintenance cost per annum for 48 houses	= 52 0 0
Maintenance cost per annum per house	= 1 1 9
Maintenance cost per house per week	= 5
Capital cost = 1d.	
Maintenance cost = 5d.	
Landscape Rent = 6d. per house per week	

Four storey development: orthodox site plan
municipal construction and maintenance of street front sites



48 houses

landscape test plan

4

LANDSCAPE TEST PLAN 3

Landscape specification			Average costs for English Municipal and New Town Corporations		Average costs for Scottish Municipal and New Town Corporations			
Item	Number		Unit cost	Sub total	Total	Unit cost	Sub total	Total
			£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
1	5 2 6 3 3 6 1 26	Acer pseudoplatanus pl. atropurpurea 12 ft.—14 ft. Acer platanus Reitenbachii, 12 ft.—14 ft. Pyrus Malus, standards Pyrus albo pleno, standards Prunus avium, 9 ft.—10 ft. Betula verrucosa, 10 ft.—12 ft. Laburnum alpinum, 10 ft.—12 ft. Stakes, felt and clout tacks Labour cost of planting trees	2 0 0 2 0 0 15 0 15 0 10 6 10 6 1 0 0 3 0	10 0 0 4 0 0 4 10 0 2 5 0 1 11 6 3 3 0 3 18 0 5 8 0	1 1 0 16 0 17 6 17 6 15 0 12 6 15 0 1 9 7 6	5 5 0 1 12 0 5 5 0 2 12 6 2 15 0 3 15 0 15 0 2 5 6 9 15 0	33 10 0	33 10 0
2	750	Mixed shrubs of undernoted species and varieties:— Cornus alba Kerria japonica Mahonia aquifolium Cornus mas Crataegus monogyna Pieris floribunda Crataegus oxyanthioides Pieris japonica Rhus typhina Cytisus praecox Rosa canina Andersonii Spartium junceum Forsythia suspensa Syringa vulgaris atrocaulis Kalmia latifolia Ulex europaeus plenus Labour cost of planting shrubs	3 3	121 17 6		4 0	150 0 0	
3		Grass seed for 2,800 sq. yds. Tilling, sowing and rolling, 2,800 sq. yds.	1 6	56 5 0	178 2 6	4	12 10 0	162 10 0
4		460 yards run, hedging, Crataegus monogyna, 2½ ft.—3 ft. Labour cost of planting hedge		210 0 0	210 0 0	2 0 3	46 0 0 5 15 0	116 13 4
5		Mixed herbaceous of undernoted species, 220 sq. yds. Achillea Iris Asters (Amellus) Kniphofia Lupinus Campanula Paeonia Corcopsis Delphiniums Solidago Spiraea Geum Helenium Heuchera Labour cost of planting herbaceous	5 0	55 0 0	117 0 0		51 15 0	51 15 0
6		350 sq. yds. of paving consisting of 2 ft. × 2 ft. pre-cast concrete slabs set in sand on a bottoming of ashes. Cost of labour and materials	1 2 0	385 0 0	385 0 0	13 0	227 10 0	227 10 0


landscape
test plan

3

7	Sandbox. Excavation, 10 cu. yds. Mass concrete foundation, 15 sq. yds. 52-ft. run, precast concrete kerb 10 tons washed pit sand Labour costs	1 0 0 8 5 0 2 9 6 16 0 5 0 0	10 0 0 8 5 0 2 9 6 5 0 0	9 0 7 0 1 6 0 6 0	4 10 0 5 5 0 7 16 0 8 0 0	25 11 0
8	Contingencies (England 20%, Scotland 5%) for replacement of trees for replacement of shrubs for replacement of herbaceous plants for replacement of hedges for resewing grass for additional topsoil	33 14 6	7 0 6 35 12 10 23 8 0 23 8 0	7 8 6 35 12 10 23 8 0 23 8 0	1 13 6 8 2 6 4 14 3 2 11 9 5 16 8	1 13 6 8 2 6 4 14 3 2 11 9 5 16 8
	Total Capital Cost		1103 17 1			687 10 0
9	Estimated cost of annual maintenance		124 2 7			71 10 0
			385 0 0		227 10 0	227 10 0

Landscape Rent per House per Week	£	s.	d.
Capital cost for 33 houses	1103	17	1
Capital cost per house	33	9	0
Assuming loan with 60-year amortization at 4½% interest			
yearly payments = £0-7726			
Weekly payments = 7½d.			
Thus capital costs can be retired by weekly payment per house of 7½d.			
Maintenance cost per annum, 33 houses	£124	2	7
Maintenance cost per annum per house	3	15	2½
Maintenance cost per house per week	1	5½	
Capital cost = 7½d.			
Maintenance cost = 1s. 5½d.			
Landscape Rent = 2s. 0½d.			

Landscape Rent per House per Week	£	s.	d.
Capital cost for 33 houses	£687	10	0
Capital cost per house	20	16	8
Assuming loan with 60-year amortization at 4½% interest			
half-yearly payments = £20-833			
£20-833 × 0-0231 = £0-4812			
weekly payments =			
£0-4812 ÷ 26 = 4½d.			
Thus capital costs can be retired by a weekly payment per house of 4½d.			
Maintenance cost per annum for 33 houses	£71	10	0
Maintenance cost per annum per house	2	3	4
Maintenance cost per house per week			10
Capital cost = 4½d.			
Maintenance cost = 10d.			
Landscape Rent = 1s. 2½d. per house per week			



landscape test plan


5

Landscape specification		Average costs in English Municipal and New Town Corporations			Average costs in Scottish Municipal and New Town Corporations		
Item	Number	Unit cost	Sub total	Total	Unit cost	Sub total	Total
1	1 1 6 1 1 2 3 15	Acer pseudoplatanus, 10 ft.-12 ft. Fraxinus excelsior, 9 ft.-10 ft. Betula verrucosa, 10 ft.-12 ft. Sorbus aucuparia, 10 ft.-12 ft. Laburnum alpinum, 10 ft.-12 ft. Prunus avium, 9 ft.-10 ft. Pyrus malus, standards Stakes, felt and clout tacks Labour cost of planting trees	£ s. d. 10 6 10 6 10 6 15 0 1 0 0 10 6 15 0 3 0 6 0 0	£ s. d. 10 6 10 6 3 3 0 15 0 1 0 0 1 1 0 2 5 0 2 5 0 6 0 0	£ s. d. 15 0 10 0 12 6 13 6 15 0 1 10 0 2 12 6 1 9 5 12 6	£ s. d. 15 0 10 0 3 15 0 13 6 15 0 1 10 0 2 12 6 1 6 3 5 12 6	£ s. d. 17 9 9 61 17 6
2	275	Mixed shrubs of undernoted species and varieties: Cornus alba Kerria japonica Cornus mas Mahonia aquifolium Crataegus monogyna Pieris floribunda Crataegus oxyanthoides Pieris japonica Cytisus albus Rosa typhina Cytisus praecox Rosa canina Andersonii Forsythia spectabilis Spartium Junceum Forsythia suspensa Syringa vulgaris atrocaulis Kalmia latifolia Ulex europaeus plenus Labour cost of planting shrubs	3 6	48 2 6	4 6	61 17 6	17 9 9
3		Grass seed for 2,275 sq. yds. Tilling, sowing and rolling 2,275 sq. yds.	1 6	170 12 6	68 15 0	61 17 6	68 15 0
4		30 yards run hedging, Lonicera nitida, 2 ft.-2½ ft. Labour cost of planting hedge	5 6	8 5 0	2 0 3	3 0 0 7 6	94 15 10
5		Mixed herbaceous of undernoted species, 110 sq. yds.: Achillea Asters (Amellus) Asilbe Campanula Coreopsis Delphiniums Geum Hedera Heuchera Labour cost of planting herbaceous	5 0	27 10 0		23 5 4	23 5 4
6		200 sq. yds. of paving consisting of 2 ft. x 2 ft. precast concrete slabs set in sand on a bottoming of ashes Cost of labour and materials	18 0	180 0 0	180 0 0	130 0 0	130 0 0


WATER HEATING | UNITS | GAS

32.C22


The Architects' Journal Library of Information Sheets 559. Editor: Cotterell Butler, A.R.I.B.A.




TYPE SG.32/1 LARGE SINGLE POINT HEATER.
swivel spout serving bath and basin




TYPE SG.32/1 LARGE SINGLE POINT HEATER.
extended swivel spout serving bath and basin



TYPE 503/0 SMALL SINGLE
POINT HEATER.
swivel spout serving two sinks



TYPE 709 MULTI-POINT HEATER.
typical flat installation



TYPE 709 MULTI-POINT HEATER.
typical two-storey house installation

32.C22 · ASCOT · INSTANTANEOUS GAS WATER HEATERS : SELECTION OF HEATERS

This Sheet is intended as a guide to the selection of suitable Ascot instantaneous gas water heaters for specific purposes. The diagrams illustrate typical heater installations; the types shown are described in detail on Sheets 32.C20, 32.C21 and 32.C24.

Ascot instantaneous gas water heaters are designed to heat water to a maximum of 100° F. above supply temperature except type RS.52/1 which will provide boiling water. The hot water service is instantaneous and unlimited and, irrespective of variations in demand, a high overall operating efficiency is maintained. Gas is only consumed when hot water is required and standby losses are reduced to a small pilot flame.

Single Point Heaters

These are of the open outlet type and must on no account be connected to any restriction in the form of taps, piping or fittings.

To facilitate hot water supply to two adjacent fittings, single point heaters are fitted with swivel spouts which are available in different lengths.

Type SG.32/1: Large single point bath heater.

Output: 1.3 gal./min. raised through 100° F.,
or 3.25 gal./min. raised through 40° F.

The top left-hand diagram shows a typical installation serving bath and adjacent basin; the top right-hand diagram shows an alternative arrangement using an extended swivel spout, the fittings for which are available from the manufacturers. The heater can also be installed to serve two adjacent sinks or a large sink in laboratory, workshop, etc.

Types 503/0, 503/1 and 503/2: Small sink heaters.

Output: 0.5 gal./min. raised through 100° F.,
or 1.25 gal./min. raised through 40° F.

These heaters are suitable for a kitchen sink, cloakroom basin or similar fitting, the centre diagram showing an installation serving two adjacent sinks.

Type RS.52/1: Small sink type boiling water heater.

Output: 2½-3 pints/min. of boiling water,
or 0.5 gal./min. raised through 104° F.,
or 1.3 gal./min. raised through 40° F.

The heater is designed for domestic use and is not suitable for continuous use in cafes or restaurants or where the water pressure exceeds 120 lb./sq. in.

Multi-point Heaters

These are of pressure proof design and can supply up to three taps connected to the heater outlet. They should be installed close to the most frequently used draw-off tap (normally at the kitchen sink) with all draw-off runs as short as possible to ensure no wastage of gas and an immediate hot water supply.

Types 709 and 709B: Multi-point heaters.

Output: 1.25 gal./min. raised through 100° F.,
or 3.25 gal./min. raised through 40° F.

The lower diagrams show typical flat and two-storey house installations. The heater will supply hot water to three cloakroom basins in schools, offices, etc., and also two showers or a Quickspray Wash Fountain. (See subsequent Sheets in this series.)

Factors Governing Choice

Number of points to be served: Single point heaters whether large or small can only serve one sink, bath or basin except where two points can be reached by a swivel spout outlet. A multi-point or several single-point heaters should be used for supply to distant draw-off points.

Rate of flow: The supply of hot water from an instantaneous heater cannot be exhausted, but the speed of delivery is limited by the size of the heater. A small heater is more efficient for limited intermittent demands than a large one and the heater, therefore, should not be larger than necessary to meet the maximum demand.

A comfortable bath temperature is 105° F., but the water should enter the bath at 120° F. to make allowance for heat losses. The times taken in supplying bath water requirements at this temperature, using heaters type 709, 709B, are given below.

Size of bath	Hot water required	Approximate time taken.
6 ft.	30 gal.	15 min.
5 ft. 6 in. ..	20 gal.	10 min.
5 ft.	15 gal.	7½ min.

Distance between points to be served: Many Water Authorities restrict the length of hot water draw-off piping from a multi-point heater in order to avoid wastage of water and the respective bye-laws should be consulted in this connection. In addition, long draw-off runs reduce the overall operating efficiency of the installation and runs approximating the maximum should be suitably lagged. Where the draw-off run from a multi-point heater would be in excess of the permissible maximum, a bath heater, type SG.32/1, should be used to serve the bath and adjacent basin and one of the 503 sink heaters, or boiling water heater type RS.52/1, used for kitchen service.

Ventilation: Adequate ventilation must be provided in any room in which an instantaneous gas water heater is installed. (See subsequent Sheets in this series.)

Flue

In the selection of heaters type SG.32/1, 709 and 709B to serve a point or points, the location of the flue (which is an essential requirement) should be considered at the initial conception of the installation. The flue installation must be efficient. (See subsequent Sheets in this series.)

Alternative Systems

Multi-point heaters are particularly suitable for connection as an ancillary to a solid fuel fired boiler installation, for summer use when the boiler supply is not required or for occasional winter use when it is not convenient to stoke the boiler. (See British Standard Code of Practice C.P. 332.201 : 1947.) For full details of alternative systems, see subsequent Sheets in this series.

Compiled from information supplied by :

Ascot Gas Water Heaters, Ltd.

Head Office

and Works : 255, North Circular Road, Neasden, London, N.W.10.

Telephone : Willesden 1234.

Telegrams : Gascot, Phone, London.

Branch Offices and

Service Depots : Belfast, Birmingham, Bournemouth and Glasgow.

Service Depots : Bristol, Cambridge, Manchester, Oxford, Southampton, Stoke-on-Trent and Jersey.

BUILDING BOARD | GENERAL DATA

15.B1 18'51

The Architects' Journal Library of Information Sheets 560. Editor: Cotterell Butler, A.R.I.B.A.

TRADE NAME	DESCRIPTION AND APPLICATIONS	THICKNESS	WEIGHT PER SQ. FT.	STANDARD SIZES
Bowater insulation board	made from long tough wood fibres — cellular construction internal use only for sound and heat insulation: for ceilings, wall linings, permanent shuttering to concrete, floor underlays	1/2 in.	0.7 lb.	6ft. 0in., 8ft. 0in., 9ft. 0in., 10ft. 0in. and 12ft. 0in. long x 2ft. 0in. and 4ft. 0in. wide
		3/4 in.	1.0 lb.	8ft. 0in. long x 3ft. 0in., 3ft. 4in. and 3ft. 6in. wide
Bowater standard hardboard	a highly compressed fibreboard giving a high degree of resistance to wear and moisture for all internal uses: wall linings and partitions panelling, flush doors, furniture etc.	1/8 in.	0.68 lb.	6ft. 0in., 8ft. 0in., 9ft. 0in., 10ft. 0in. and 12ft. 0in. long x 4ft. 0in. wide
		3/16 in.	1.0 lb.	6ft. 6in. long x 2ft. 6in. wide 8ft. 0in. long x 5ft. 0in. wide
Bowater leathergrained hardboard	as Bowater standard hardboard but with one surface patterned during manufacture to produce a leather-grain effect	1/8 in.	0.68 lb.	6ft. 0in. and 9ft. 0in. x 4ft. 0in. wide 8ft. 0in. long x 5ft. 0in. wide
Bowater reeded hardboard	a standard hardboard patterned during manufacture with lengthwise reeds, 3/4 in. wide for internal uses: dados, wall linings, partitions fascias, counter fronts etc.	1/8 in.	0.68 lb.	6ft. 0in. and 9ft. 0in. long x 4ft. 0in. wide
Bowater perforated hardboard	a standard hardboard perforated with 3/16 in. holes at 1/2 in. or 3/4 in. centres for internal uses: window displays, exhibition stands, pegboards etc. board perforated at 1/2 in. centres for facing fibrous sound-absorbents	1/8 in.	0.62 lb.	6ft. 0in. and 9ft. 0in. long x 4ft. 0in. wide
Bowater super hardboard	similar material to standard hardboard but hardened by a special process to give superior strength and surface for internal or external use: concrete form-lining, floor covering etc.	1/8 in.	0.72 lb.	6ft. 0in., 8ft. 0in., 9ft. 0in., 10ft. 0in. and 12ft. 0in. long x 4ft. 0in. wide
		3/16 in.	1.05 lb.	8ft. 0in. long x 5ft. 0in. wide

BOWATER BOARDS: RANGE, STANDARD SIZES AND TYPICAL APPLICATIONS.

Manufacturer: Building Boards Division, Bowaters Sales, Company Limited.

15.B1 BOWATER BOARDS: RANGE, STANDARD SIZES AND TYPICAL APPLICATIONS

This Sheet supersedes Sheet 15.B1 published 26.5.55 and tabulates the range of Bowater insulation and hardboards and gives standard sizes, properties and typical applications for each type.

Bowater insulation boards have a low thermal transmission value (conductivity $k = 0.35$ B.t.u./ft.²hr./deg. F. 1 in. thickness). The sound absorption coefficient is 0.30 (average) on 2 in. by 1 in. nominal battens at 1 ft. 4 in. centres. As a base for plaster these boards minimise drumming.

Thermal conductivity of a sample of Bowater $\frac{1}{2}$ in. insulation board (approximate density of insulation board : $16\frac{1}{2}$ lb. per cu. ft.):

Cold face temperature		Hot face temperature		Thermal conductivity	
Deg. C.	Deg. F.	Deg. C.	Deg. F.	Gram. cal. per sq. cm. per second for 1 cm. thickness and 1 deg. C. difference in temperature	B.Th.U. per sq. ft. per hour for 1 in. thickness and 1 deg. F. difference in temperature
18	64	30	86	0.00012	0.35

Bowater standard hardboard: This is manufactured entirely of wood fibres highly compressed to give a high degree of resistance to wear and moisture. The board is of a homogeneous nature and rich brown

in colour, glazed on one face and textured on the other. Although the natural finish is pleasing, it also provides an excellent base for all forms of decoration, as described on Sheet 15.C4. Boards can be cut and worked with ordinary woodworking tools and can be bent to any reasonable curve without steam.

Bowater leathergrained hardboard: This is similar to standard hardboard but one surface is patterned during manufacture to represent a leather grain.

Bowater reeded hardboard: Standard hardboard patterned during manufacture with lengthwise reeds, $\frac{3}{4}$ in. wide.

Bowater perforated hardboard: Standard hardboard perforated with $\frac{3}{8}$ -in. holes at $\frac{1}{2}$ -in. or $\frac{3}{4}$ -in. centres.

Bowater super hardboard: This is similar to standard hardboard, but possessed of greater strength, moisture resistance and wearing properties. It is specially recommended for concrete form lining, floor covering, van bodies and all external uses.

Compiled from information supplied by:

Building Boards Division,
Bowaters Sales Company Limited.


Address : Bowater House, Stratton Street, London, W.1.

Telephone : Mayfair 8080.

Irish Wallboard Company Limited.



Address : Athy, County Kildare.

Telephone : Athy 80.



CONSTANT HEAT

...WITH LOCAL COAL



Riley Class 'B' Stokers firing Ruston Horizontal Boilers at a northern hospital.

An important aid in an operating theatre is constant temperature — sometimes difficult to maintain with present coal supplies.

A Riley Automatic stoker maintains even boiler heat and makes the most of available coal. Scores of hospitals, industries and offices save fuel, cut costs, and enjoy smokeless combustion with Riley stokers. They can be fitted to all normal types of boiler. Write for further details.

Fuel saving is automatic with

RILEY STOKERS

RILEY (IC) PRODUCTS LIMITED
(Mechanical Stokers • Syntron Electric Vibratory Equipment)


NINETEEN WOBURN PLACE • LONDON W.C.1 • TERMINUS 2622 • Member of the International Combustion Organisation

Now - still greater value and dependability!



Never before has such an outstanding flush door been offered at such a moderate price. Already recognised as the finest door obtainable at the price, the DURADOR with the unique "PLACAROL" core is now a "better-buy" than ever.

*Note these outstanding features —
then ask us to quote you*



The "PLACAROL" Core

An entirely new principle, the "PLACAROL" core comprises hundreds of closely packed wood spirals bonded in an immovable unity with the plywood facings. This unconventional use of a traditional material provides a core which is unrivalled for strength, uniformity and surface support — and it's exclusive to HILLS OF STOCKTON.

- No more surface undulation and "shadow" cores.
- Far greater strength and stability with an appreciable saving in weight.
- Uniform support for the plywood faces.
- Kiln-dried framing and lock blocks of ample size
- Faced with balanced West African plywood of our own manufacture.
- Available in paint or stain and varnish grades.
- Finished thickness 1 1/4".
- Guaranteed for three years.

F. HILLS & SONS LTD., Norton Road, Stockton-on-Tees

TELEPHONE: STOCKTON 67141 (7 lines)

London Branch Office:

28 Victoria Street, Westminster, S.W.1. Telephone: ABBey 6542


For London & Southern Counties users,

Stocks of all Hills Doors are held at our London Depot.

7	Sandbox Excavation, 8 cu. yds. Mass concrete foundation, 12.5 sq. yds. 48 ft. run, precast concrete kerb 8 tons washed pit sand	1 0 0	8 0 0	28 6 9	21 2 6
8	Contingencies (England 20%, Scotland 5%) for replacement of trees for replacement of shrubs for replacement of herbaceous for resowing of grass } 5 per cent. for additional topsoil		3 10 0 13 15 0 5 10 0 1 12 6 8 5 6	3 10 0 13 15 0 5 10 0 1 12 6 8 5 6	17 6 3 8 9 2 6 6 3 3 4 14 9
9	Total Capital Cost Estimated cost of annual maintenance			533 12 3 87 8 6	11 10 9 370 6 8 69 6 8

Landscape Rent per House per Week	£ s. d.
Capital cost for 80 houses	370 6 8
Capital cost per house	4 12 7
Assuming loan with 60 year amortization at 4½ per cent. interest, half yearly payments = £4.629	
× 0.0231 = £1069	
Weekly payments = £0.1069 ÷ 26 = £0.004	
Thus capital costs can be retired by a weekly payment per house of 1d.	
Maintenance cost, per annum for 80 houses	= 69 6 8
Maintenance cost, per annum per house	= 17 4
Maintenance cost, per house per week	= 4
Capital Cost	= 1d.
Maintenance Cost	= 4d.
Landscape Rent	= 5d. per house per week

Landscape Rent per House per Week	£ s. d.
Capital cost for 80 houses	533 12 8
Capital cost per house	6 13 5
Assuming loan with 60 year amortization at 4½ per cent. interest, half yearly payments = weekly payments = 6.67 × 0.0231 = 10.006 = 13d.	
Thus capital costs can be retired by weekly payments of 13d. per house	
Maintenance cost per annum, per house	= 13d.
Maintenance cost per house per week	= 5d.
Capital cost	= 13d.
Maintenance cost	= 5d.
Landscape Rent	= 6½d.



TECHNICAL SECTION

CURRENT PRICES FOR MEASURED WORK

Prepared by Davis, Belfield & Everest, chartered quantity surveyors

Prices are for work executed complete and are for an average job in the London area. All prices include overhead charges and profit for the general contractor. Current prices of materials and rates of wages last appeared in the JOURNAL for February 9

PRELIMINARIES

To all valuations for measured work add for Preliminaries, Water and Insurances, according to the nature of the job (say) 10%

EXCAVATOR

Excavation

N.B.—The following prices are applicable to hand excavation in heavy soil.

Surface digging, 6" deep	Yd. super	1/1
Ditto, 12" deep	"	2/2
Excavating not exceeding 10' 0" deep to reduce levels	Yd. cube	8/10
Excavating not exceeding 5' 0" deep to form basement	"	10/-
Ditto exceeding 5' 0" and not exceeding 10' 0" deep ditto	"	14/5
Excavating not exceeding 5' 0" deep to form surface trenches	"	12/2
Ditto exceeding 5' 0" deep and not exceeding 10' 0" deep ditto	"	16/8
Excavating not exceeding 5' 0" deep to form basement trench commencing 10' 0" deep	"	21/1

Disposal

Returning, filling and ramming around foundations	Yd. cube	3/11
Wheeling excavated soil not exceeding 100 yards and depositing	"	4/5
Ditto and spreading and levelling	"	5/9
Ditto, ditto, and consolidating to make up levels under floors and pavings	"	7/4
Filling into lorries and carting away	"	14/1

EXCAVATOR—(continued)

Planking and Strutting

Planking and strutting to sides of surface or basement excavation not exceeding 5' 0" deep	Ft. super	-/7
Ditto not exceeding 10' 0" deep	"	-/9
Planking and strutting to sides of surface trenches not exceeding 5' 0" deep (both sides measured)	"	-/2
Ditto not exceeding 10' 0" deep (ditto)	"	-/3

Hardcore

Hardcore filled in, in layers, each layer well rammed with a mechanical rammer	Yd. cube	19/2
Bed of ditto, 4" thick	Yd. super	3/2

CONCRETOR

Concrete (Basic Prices)

Portland cement concrete 1 : 3 : 6 with 1½" coarse aggregate in foundations and masses exceeding 12" thick	Yd. cube	68/10
Ditto 1 : 2 : 4 with ½" coarse aggregate ditto	"	75/2
<i>Add to basic prices for:—</i>		
Working around rod or mesh reinforcement	"	4/5
Being in beds less than 12" thick (6"-12")	"	2/3
Ditto less than 6" thick (4½"-6")	"	6/8
Being in small quantities not exceeding 3' cube	"	17/9
Being in suspended floors and roofs	"	13/4
Being in walls not exceeding 6" thick	"	22/2
Ditto exceeding 6" but not exceeding 12" thick	"	15/6
Ditto exceeding 12" thick	"	11/1

CONCRETOR—(continued)

Add to Basic Prices for:—

Being in lintels, beams, etc., not exceeding 72 sq. in. sectional area	Yd. cube	33/3
Ditto exceeding 72 and not exceeding 144 sq. in. sectional area	"	26/7
Ditto exceeding 144 sq. in. sectional area	"	22/2
Being in columns not exceeding 72 sq. in. sectional area	"	42/2
Ditto exceeding 72 and not exceeding 144 sq. in. sectional area	"	33/3
Ditto exceeding 144 sq. in. sectional area	"	26/7

Formwork

Flexible formwork to soffits of barrel vault roofs	Yd. super	20/-
Close boarded formwork and supports to soffits of floors not exceeding 12' high	"	16/7
Ditto to vertical faces of walls (both sides measured)	"	16/9
Ditto to sides and soffits of lintols and beams	Ft. super	2/5
Add to the above for wrot boarded formwork and rubbing down concrete	Yd. super	3/-

Reinforcement

½" to 1" diameter mild steel rod reinforcement, hooked, bent and tied at intersections as required and fixing in concrete	Cwt.	56/9
½" diameter ditto	"	63/5
¾" diameter ditto	"	82/1
Steel wire mesh fabric reinforcement to B.S. 1221, weighing 4.71 lb. per yard super, well lapped at joints and embedded in concrete	Yd. super	3/9
Ditto weighing 9.32 lb. per yard super ditto	"	7/3

BRICKLAYER

Common Brickwork

		Flettons	Rough stocks
Reduced brickwork one brick thick in cement-lime mortar (1 : 3 : 9)	Yd. super	31/5	38/-
Add to the above:—			
If in cement mortar (1 : 3)	"	-/3	-/3
If circular on plan to flat sweep	"	5/2	5/7
Ditto to quick sweep	"	10/4	11/1
Half brick wall in cement lime mortar (1 : 3 : 9)	"	17/1	20/4
Ditto built fair and pointed both sides with a neat flush joint	"	19/4	22/8
One brick wall built fair and pointed both sides with a neat flush joint	"	37/3	43/10
11" hollow wall with 2" cavity and galvanized iron twisted ties	"	37/1	43/8

Engineering Brickwork

		Lingfield Wirecuts	Blue Pressed bricks
Reduced brickwork one brick thick in cement mortar (1 : 3)	Yd. super	47/3	83/10
Half brick wall in cement mortar (1 : 3)	"	25/6	44/1
Ditto built fair and pointed both sides with a neat flush joint	"	27/8	47/1
One brick wall built fair and ditto	"	52/1	89/4

Sundries

Extra for internal fair face and flush pointing	Yd. super	1/3
Horizontal damp-proof course of two courses of slates and bedding and pointing	Ft. super	4/-
Ditto of hessian base bitumen well lapped at joints	"	-/10
Fixing only metal window, size 1' 8" × 4' 0", including cutting and pinning lugs to brickwork, bedding frames and pointing in mastic one side	Each	9/2
Ditto, 3' 3" × 4' 0" ditto	"	14/2
Ditto, 6' 6" × 4' 0" ditto	"	25/-

Partitions

		2"	2½"	3"	4"
Clinker concrete solid partition blocks to B.S. 2028 (Type B and O) and setting in cement mortar	Yd. super	8/8	10/1	11/11	14/6
Hollow clay partition blocks to B.S. 1190, keyed on both sides and ditto	"	9/4	10/4	12/-	14/11
Moler hollow partition blocks, keyed on both sides and ditto	"	20/-	21/6	23/4	28/1

BRICKLAYER—(continued)

Facings

		Ordinary facings, p.c.	White glazed facings p.c. for stretchers	White glazed facings p.c. for headers and pointing with white cement
Extra over common brickwork built with bricks p.c. 113/- M for facings as described and pointing with a neat weathered joint:—		256/6	271/4	92/8
To solid wall in Flemish bond	Yd. super	15/8	16/9	1480/6M
To cavity wall in stretcher bond	"	12/10	13/8	74/4
To ditto in Flemish bond with snapped headers	"	15/3	16/3	—
Half brick wall in facings in stretcher bond built fair and pointed one side with a neat weathered joint	"	28/7	29/5	—
Ditto pointed both sides	"	29/9	30/6	—
One brick wall in facings built fair and pointed one side	"	53/3	54/10	—
Ditto pointed both sides	"	54/5	56/-	—
Brick on end flat arch in facings 4½" on soffit and 9" high and pointing	Ft. run	3/4	3/5	—
Brick on edge coping to 9" wall with two courses plain tiles under, laid breaking joint, two cement angle fillets and pointing	"	5/6	5/7	—

ASPHALTER

Tanking

		To B.S. 1097	To B.S. 1418
Horizontal asphalt tanking in three thicknesses on brick or concrete	Yd. super	18/5	29/5
Vertical ditto	"	23/8	33/7

Roofing

		To B.S. 988	To B.S. 1162
½" asphalt flat in two thicknesses on and including felt underlay	Yd. super	13/2	22/1
Asphalt skirting 6" high with angle fillet at bottom and rounded top, turned into groove	Ft. run	2/4	2/7
Asphalt fascia 6" high with solid water check roll at top and undercut drip at bottom	"	4/6	5/3

DRAINLAYER

Trenches and Beds

N.B.—The following prices are applicable to hand excavation in heavy soil, only requiring planking and strutting for depths of 3' or more.

Excavate trenches for 4"-9" pipes, including planking and strutting, filling in and ramming, and wheeling and spreading surplus:—		
For each 12" in depth, for trenches not exceeding 3' 0" deep	Yd. run	3/7
Ditto for trenches exceeding 3' 0" and not exceeding 5' 0" deep	"	5/-
Ditto for trenches exceeding 5' 0" and not exceeding 10' 0" deep	"	8/-
6" concrete (1 : 3 : 6) bed and benching for pipes	Yd. run	9/4
6" ditto, and surround	"	15/2

Drains

		3"	4"
Clayware butt-jointed land drains and laying in trench	Ft. run	-/5	-/6
"Seconds" quality glazed stoneware socketed drains and laying and jointing in trench	"	2/3	3/3
"British Standard" quality ditto	"	2/8	3/11
Extra on "Seconds" quality for bends	Each	3/7	5/3
Ditto "British Standard" quality ditto	"	4/5	6/6
Extra on "Seconds" quality for equal single junction	"	6/1	8/9
Ditto "British Standard" quality ditto	"	7/5	10/10

DRAINLAYER—(continued)

Cast iron socketed drains to B.S. 437 and laying and jointing in trench	Ft. run	4" 12/8	6" 19/1	9" 37/11
Extra for short radius bend	Each	26/1	62/10	165/6
Extra for single junction	"	47/9	105/2	273/8

Fittings, etc.

Glazed stoneware trapped gully with galvanized grating and outlet and setting in concrete	Each	4" 25/-	6" 46/5	
Ditto with vertical inlet ditto	"	31/1	52/7	
Cast iron trapped gully with high invert, grating, and 4" outlet and setting in concrete	"	73/8	—	
Ditto with vertical inlet ditto	"	84/-	—	
Glazed stoneware intercepting trap with inspection arm, stopper and chain and fixing in manhole and jointing to drain	"	79/4	92/4	
Brown glazed stoneware half round straight channels and bedding and jointing in cement mortar	Ft. run	2/1	3/1	
Ditto ordinary channel bend and ditto	Each	6/2	8/8	
Cast iron coated single seal manhole cover and frame to B.S. 497 Grade C and setting frame in cement and cover in grease	"	24" × 18" 47/3	24" × 24" 69/9	
Galvanized ditto	"	79/3	120/3	

PAVIOR

Cement and sand (1:3) floated screed to receive pavings	Yd. super	3" 3/10	1 1/2" 4/8	1 1/4" 5/3
Ditto trowelled smooth to receive linoleum	"	4/3	5/1	5/8
Cement and sand (1:3) paving trowelled hard and smooth	"	4/3 1/2	5/1 1/2	5/8 1/2
Granolithic paving (1:2 1/2) laid on concrete	"	6/8	7/7	8/6
1/2" red composition paving to B.S. 776 laid on prepared screed	Yd. super			16/7
1/2" terrazzo paving (Portland cement and spar aggregate) laid on prepared screed	"			34/2
Extra for white or cream cement	"			5/3
1/2" rubber flooring in all colours, laid on prepared screed	"			55/2
1/2" × 12" × 12" rubber tile flooring ditto	"			45/8
1/2" × 12" × 12" cork tile flooring (brown shades) laid in mastic on prepared screed, surfaced and polished	"			45/11
6" × 6" red quarry tile paving to B.S. 1286 laid on prepared screed with straight joints	Yd. super	26/9	30/3	34/4
6" × 6" buff quarry tiles as last	"			
2 1/2" (finished) gravel path laid on prepared bed, well watered and rolled to cambers and falls	"		3/-	

MASON

Portland stone and all labours in pilasters, and quoins	Ft. cube	49/7		
Ditto in jambs, lintols, etc.	"	51/10		
Ditto in arches	"	65/-		
Ashlar av. 6 1/2" on bed with plain dressed face	Ft. super	29/3		
Portland stone or artificial stone to B.S. 1217:—	Port-land	Arti-ficial		
4 1/2" × 4" sill, sunk, weathered, throated and grooved for water bar, set and jointed in cement mortar	Ft. run	10/3	4/5	
9" × 3" ditto	"	13/6	6/9	
2" × 12" Coping, weathered and twice throated, set and jointed as last	"	12/-	5/10	
3" × 12" Ditto	"	16/2	8/11	
5" × 12" Saddle back coping twice throated, set and jointed as last	"	25/4	13/7	
6" × 12" Ditto	"	32/-	15/4	

SLATER, TILER AND ROOFER

Best Bangor slates to B.S. 680 laid with 3" lap, each slate nailed with two stout copper nails	Square	351/9	283/6	
Ditto hung vertically to dormer cheeks and gables	"	357/-	291/4	

SLATER, TILER AND ROOFER—(continued)

		Tiles		Hand made	Machine made
Best sand faced plain (nibbed) tiles to B.S. 402, 10 1/4" × 6 1/4" laid to a 4" gauge with each tile in every fourth course nailed with galvanized nails	Square			205/9	185/3
Ditto hung vertically to dormer cheeks and gables to 4 1/2" gauge with each tile nailed with galvanized nails	"			225/9	203/9
Berkshire hand made sand faced red pantiles 14 1/4" × 10" laid to 2 1/4" head and 1 1/4" side laps, each tile in every third course nailed with galvanized nails	Square			205/3	
Ditto to mansard slopes	"			221/-	
Bridgwater hand made Double Roman red sandfaced tiles 16 1/4" × 14" laid to 3" laps, each tile in every course nailed with galvanized nails	"			139/8	
Concrete plain (nibbed) tiles to B.S. 473, 10 1/4" × 6" laid as before described for plain tiles	"			121/9	
Ditto hung vertically to dormer cheeks, and gables, ditto	"			150/2	
Concrete interlocking tiles 15" × 9" laid to 3" lap, each tile in every third course nailed with galvanized nails	"			94/6	
Ditto to mansard slopes ditto	"			100/9	

Asbestos Cement

6" corrugated asbestos cement sheeting fixed to wood roofs with galvanized drive screws and washers with a side lap of 1 1/2 corrugations and an end lap of 6"	"			110/9	
6" ditto but fixed vertically	"			121/3	
Add to both last if fixed to steel purlins or sheeting rails with galvanized hook bolts	"			5/3	

Felt

Reinforced bituminous roofing felt laid with 3" laps and nailed to rafters at 18" centres with galvanized clout nails	"			21/3	Three layer
One-ply bitumen felt to B.S. 989 laid on concrete. Each layer bedded in hot bitumen	Yd. super	9/5	12/7		
Extra on last for finishing with granite chippings	"	-9/1	-9/1		

CARPENTER*Carcassing*

Softwood, sawn and fixed, in plates, sleeper joists and lintols	Ft. cube	16/5		
Ditto in floor and ceiling joists	"	18/6		
Ditto in stud partitions, purlins and struts	"	20/5		
Ditto in rafters, framing and ridge	"	20/3		
Ditto in hip and valley rafters including cutting rafters to sizes	"	22/9		

Battening and Boarding

		Roof slopes	Vertical hanging
1" × 2" battens nailed to softwood for 20" × 10" slates to 8 1/2" gauge	Square	32/3	34/5
Ditto 16" × 10" slates to 6 1/2" gauge	"	42/-	45/2
1" × 1 1/2" ditto for 10 1/2" × 6" tiles to 4" gauge (4 1/2" for vertical hanging)	"	54/7	52/6
1" × 2" ditto for 14 1/4" × 10" pantiles to 12" gauge	"	23/1	25/3
1" × 1 1/2" ditto for 15" × 9" concrete interlocking tiles to 12" gauge	"	18/4	19/5
Roof boarding in batten widths close jointed and fixed to flat or sloping roofs	"	122/-	151/8
Ditto tongued and grooved and prepared for felt roofing including furring to falls	"	181/4	212/6
Sawn gang boarding fixed to joists in roof	Ft. super	1/4	1/8
Wrot and cross-tongued eaves soffit	"	2/2	2/6
6" wrot and grooved eaves fascia planted on	Ft. run	1/-	1/2

Wall and Ceiling Boards

		Vertically	Soffits
1" fibre board to B.S. 1142 fixed with galvanized flat headed nails to softwood	Yd. super	6/-	6/2
3/8" asbestos cement flat sheeting to B.S. 690 fixed as last	"	7/8	8/1
1" ditto	"	9/1	9/7

JOINER

Floors and Skirtings

(All thicknesses stated are nominal)

Plain edge softwood flooring in batten widths nailed to floor joists	Square	152/-	169/3	203/6
Tongued and grooved ditto	"	162/3	180/3	216/-
1" double grooved and tongued and grooved wood block floor laid herringbone with two-block border, set in hot mastic composition on prepared screed and wax polished:—				
Swedish softwood	Yd. super	29/-		
European beech	"	34/2		
English oak	"	46/3		
European oak	"	41/-		
Burma teak	"	46/3		
Australian jarrah	"	37/10		
Softwood skirtings with splayed or molded top edge, planted on (per inch sectional area)	Ft. run	-2 1/4	-2 1/4	
Extra for grounds plugged to brickwork	"	-	-8	

Windows in Softwood

Rebated and molded softwood fanlights and casement sashes divided into squares for glass	Ft. super	1 1/4	2"	
Extra for hanging	Each	5/6	5/6	
Cased frames with 6" x 3" oak sill and 2" molded double hung sashes including pulleys, line and weights	Ft. super	—	11/-	
N.B.—The above prices are for purpose made joinery. Standard pattern casement windows and double hung sashes and frames to B.S. 644 are cheaper.				

Doors in Softwood

Framed ledged and braced doors filled in with 1" T. & G. and V-jointed boarding and hanging	Ft. super	1 1/4	1 1/4	2"
Four-panel door, square both sides	"	4/5	5/7	5/7
Ditto molded one side	"	4/8	5/10	5/10
Ditto molded both sides	"	4/11	6/2	6/2
N.B.—The above prices are for purpose made doors. Standard panelled doors to B.S. 459 are cheaper.				
1 1/2" standard flush doors 2' 6" x 6' 6" internal pattern	Each	49/7		
2" ditto 2' 9" x 6' 6" external pattern	"	76/7		

Linings, Frames, etc., in Softwood

Window and door linings etc. (per inch in sectional area)	Ft. run	Sectional area Up to 6" 6" to 12"		
Frames wrot all round and framed (ditto)	"	-4	-3 1/2	
Mullions, transoms and cills (ditto)	"	-3	-3	
Moldings, architraves, etc. (ditto)	"	-3 1/2	-3 1/2	
6" Window boards with rounded nosings, tongued at back and including bearers	"	2" to 4" 4" to 6"		
Extra for each additional 3" width	"	Thickness 1" 1 1/4"		
	"	2/10	3/1	
	"	-6 1/2	-8	

Shelving and Fittings in Softwood

Shelving of 2" slats spaced 1" apart on bearers (measured separately)	Ft. super	2 1/2	2/5	
Shelving on ditto	"	2/2	2/9	
Cross tongued shelving on ditto	"	2/5	3/-	
Shelving 9" wide on ditto	Ft. run	1/10	2/2	
2" shelf bearers plugged to walls	"	-7	-10	
The following in framed up cupboard fittings:				
T. & G. & V-jointed back	Ft. super	3/4	4/2	
Cross tongued top, bottom shelf or division	"	3/5	4/3	
1 1/2" flush cupboard doors	"	5/3		
Labour rebate or groove	Ft. run	-2		
Labour cross-grain	"	-2 1/4		
1" x 2" bearers screwed on	"	-8		

N.B.—The above prices are for purpose-made cupboard fittings. Standard pattern kitchen fittings to B.S. 1195 are cheaper.

IRONMONGERY

3" steel butts (medium quality)	Pair	Soft-wood 5/6	Hard-wood 6/9
4" ditto (ditto)	"	7/4	8/11
Double action floor springs and top centres including filling boxes with oil P.C. 149/3	Each	184/3	190/10
Overhead check action door springs, P.C. 66/8	"	85/10	90/-

IRONMONGERY (continued)

6" barrel bolts	P.C. 5/6	Each	Soft-wood 7/10	Hard-wood 8/5
Cupboard locks	P.C. 8/2	"	12/9	14/-
Norfolk latches	P.C. 5/6	"	11/1	12/9
Cylinder night latch	P.C. 15/11	"	23/9	25/10
Mortice latch	P.C. 9/4	"	15/3	16/11
Rim lock	P.C. 10/-	"	14/9	16/-
Mortice lock	P.C. 15/2	"	22/11	25/1
Door furniture	P.C. 24/-	Set	27/8	28/-
Sash fasteners	P.C. 9/-	Each	11/11	12/7
Casement fasteners	P.C. 7/11	"	10/3	10/9
Casements stays	P.C. 11/6	"	14/2	14/8

STEEL AND IRONWORKER

Structural Steelwork

The following prices are for Basic sections only. Prices for other sections vary roughly in proportion to the price of the steel ex mills—see "Current Market Prices of Materials."

R.S.J.—in steel framed structures hoisted and fixed complete	Ton	£ s. d.	66 0 0
Riveted compound girders including plates and rivets	"	77 0 0	
R.S. stanchions including caps, bases, cleats, etc.	"	76 0 0	
Riveted compound stanchions ditto	"	80 10 0	
Riveted roof trusses with flat and angle members, plates, cleats, etc., 30' span	"	108 0 0	
Ditto 40' span	"	102 0 0	

Sundries

Simple wrot iron balustrades fixed complete (excluding mortices etc.)	Cwt.	12 2 0
Bolts with heads, nuts and washers and fixing	"	12 2 6

PLASTERER AND TILE FIXER

24 gauge expanded metal lathing and fixing to softwood soffits	Yd. super	6/-
--	-----------	-----

Lime and Gypsum Plaster

Three coat lime and two coat "Sirapite" or similar gypsum plaster:—			
On brick walls and partitions	Yd. super	Lime 6/10	Sirapite 5/3
On concrete soffits including hacking	"	8/3	7/7
On soffit of E.M.L. (measured separately)	"	7/1	8/3
3/4" Gypsum plasterlath fixed to softwood soffits, in accordance with manufacturer's instructions, finished with setting coat of suitable plaster	Yd. super	8/2	
Plaster moulded cornice or cove (per inch in girth)	Ft. run	-5	

Cement Rendering

Rendering in Portland cement lime sand (1:1:6) and setting in Keenes cement on brick walls and partitions	Yd. super	6/6
Portland cement and sand (1:3) plain face trowelled smooth on ditto	"	6/-
Portland cement and sand (1:3) screed for tiling on ditto	"	3/2

Wall Tiler

6" x 6" x 1/2" standard quality white glazed wall tiles set and jointed on prepared screed	Yd. super	43/-
Ditto eggshell matt or glossy glazed enamelled	"	55/2

EXTERNAL PLUMBER AND COPPERSMITH AND ZINC WORKER

Milled sheet lead and labour	Cwt.	236/3	Gutters, flash-ings, etc.	Stepped flash-ings
24 S.W.G. sheet copper and labour	Ft. super	6/9	7/1	7 4
23 S.W.G. sheet copper and labour	"	7/-	7/4	7/7
14 gauge zinc and labour	"	2/10	3/1	3/3
20 S.W.G. super purity aluminium and labour	"	5/-	5/1	5/1
20 S.W.G. commercial quality aluminium and labour	"	3/11	4/-	4/-

Rainwater Pipes and Gutters

Cast iron medium section (3/4" metal) R.W. pipes and jointing and fixing to walls with pipe nails and distance pieces or holderbats (cutting and pinning holderbats measured separately)	Ft. run	5/9	4/7	6/10	5/9
			3"	4"	
			With bats	With nails	With With holder- bats holder- nails nails

EXTERNAL PLUMBER AND COPPERSMITH AND ZINC WORKER—(continued)

		3"		4"	
		With holder bats	With nails	With holder bats	With nails
Pressed steel R.W. pipes and ditto	Ft. run	24 G. 4/1	3/5	20 G. 5/10	5/-
Asbestos cement R.W. pipes and ditto	"	3/1	—	5/-	—
Cast iron half round eaves gutter and jointed and fixed with brackets to fascia	"	4" 3/5	3/10	6" 4/11	5/10
Ditto O.G. ditto	"	3/8 1/2	4/8	5/4	7/2
18 Gauge pressed steel half round ditto	"	3/-	—	4/-	—
Ditto O.G. ditto	"	3/7	—	4/11	—
Asbestos cement half round ditto	"	2/7	—	3/11	—

Soil and Ventilating Pipes

		3"		4"	
		Heavy	Med-ium	Heavy	Med-ium
Lead soil, waste and ventilating pipes (17 lb. per yard for 3" and 22.8 lb. per yard for 4" diameter) fixed to walls with lead tacks and brass screws	Ft. run	14/6	—	20/3	—
Medium or heavy section cast iron soil, waste and ventilating pipes with caulked joints, fixed to walls, with pipe nails and distance pieces	"	6/1-	5/7	7/11	7/7

INTERNAL PLUMBER

Lead Pipes

Prices are based upon the following weights per yard.

		1 1/2"	1"	3/4"	1 1/4"
		lb.	lb.	lb.	lb.
Supply	7	11	16	21
Distributing	6	9	12.5	16
Flushing and overflow	3	5	7	9
Waste and ventilating	—	—	—	7
Supply pipe in trench (measured separately)	Ft. run	4/7	6/11	9/10	13/-
Ditto fixed to walls and ceilings	"	5/1	7/7	10/9	14/4
Distributing pipe fixed to walls and ceilings	"	4/7	6/6	8/10	11/7
Flushing and overflow pipe ditto	"	2/11	4/5	5/10	7/8
Waste and ventilating pipe ditto	"	—	—	—	6/11
Joints to fittings	Each	5/9	6/9	7/4	8/1
Bends	—	—	—	2/3
Branch joints	7/3	8/6	9/-	10/7

Steel Tubes and Fittings

Galvanized steel tubes to B.S. 1387 Class C with screwed joints in red lead as supply pipe laid in trench (measured separately)	Ft. run	2/3 1/2	2/7	2/9	3/4 1/2
Ditto Class B ditto fixed to walls and ceilings as supply, distributing, waste pipe, etc.	"	2/2	2/6	2/7 1/2	3/3
Joints to fittings	Each	4/3 1/2	5/-	5/10 1/2	7/-
Bends	—	—	4/3 1/2	6/1 1/2
Tee, equal or reducing	"	2/6 1/2	3/-	3/6	4/10

Copper Tubes and Fittings

Prices are based upon the following gauges :-

		1 1/2"	1"	3/4"	1 1/4"
		18	17	16	16
Supply	19	19	18	18
Distributing, waste, etc.	19	19	18	18
Copper tubes to B.S. 1386, as supply pipe laid in trench (couplings and trench measured separately)	Ft. run	2/5 1/2	3/8	5/1	6/5
Ditto to B.S. 659 as distributing, waste pipes, etc., fixed to walls and ceilings. Couplings measured separately	"	2/6 1/2	3/1	4/3 1/2	5/3
Brass compression type couplings—copper to copper	Each	5/4	6/3	8/7	10/10
Ditto bends	6/11	8/2	11/8	14/6
Ditto tees	9/-	10/2	15/6	22/4

Sanitary Fittings

Fireclay sinks 24" x 18" x 10" including cutting and pinning brackets to tiled wall. P.C. 75/-	Each	£ s. d.	5 16 0
Combined metal sink and drainer 42" x 18" x 8 1/4" to bearers (measured separately). P.C. 330/-	"	19 0 0	

INTERNAL PLUMBER—(continued)

Fireclay lavatory basin 25" x 18" with taps and towel rail bracket including screwing brackets to tiled wall. P.C. 138/6	Each	£ s. d.	8 15 0
Rectangular cast iron porcelain enamelled bath 5' 6" long, with taps, and panels to side and one end fixed to framing (measured separately) P.C. 390/6	"	23 0 0	
Fireclay w.c. pan with trap, plastic seat, high level cistern and flush pipe, including screwing pan to floor and cistern brackets to backboard. P.C. 200/-	"	12 10 0	
Ditto with low level cistern P.C. 240/-	"	14 10 0	

GLAZIER

		To wood	To metal
18 oz. Ordinary quality sheet glass and glazing with putty in squares not exceeding 4 ft. sup.	Ft. super	1/3	1/6
24 oz. Ditto and ditto	"	1/5 1/2	1/8
32 oz. Ditto and ditto	"	2/-	2/2 1/2
1/2" figured, rolled, and cathedral—untinted and ditto	"	1/8	1/9 1/2
1/4" rough cast and ditto	"	2/-	2/2
1/4" wired cast and ditto	"	2/2 1/2	2/5
1/4" Georgian wired cast and ditto	"	2/2 1/2	2/5
1/4" Georgian wired polished plate and ditto	"	6/11 1/2	7/1
1/4" polished plate (glazing quality) and ditto (In squares 5-45 ft. super).	"	6/11 1/2	7/1

PAINTER

Whitening, Distemper and Paint on Walls

Prepare and twice whiten plastered ceilings	Yd. super	1/3
Prepare and twice distemper with washable distemper on plastered walls and ceilings	"	1/10
Ditto on brick or concrete	"	2/5
Prepare and paint two coats emulsion paint on plastered walls	"	2/8
Prepare, prime, and paint two coats oil colour on plastered walls and ceilings	"	4/11

Paint on Metal

		Basic price	Add for each additional coat
Prepare, prime, and paint one coat oil colour on general surfaces	Yd. super	3/2	1/6
Ditto metal casements	"	5/-	2/3
Ditto members of roof trusses	"	4/1	1/10
Ditto balustrades one side	"	5/-	2/3
Ditto bars, etc., not exceeding 6" girth	Yd. run	-/10	-/4 1/2
Ditto small pipe	"	-/10	-/4 1/2
Ditto large pipe	"	1/8	-/9

Paint on Wood

		Basic price	Add for each additional coat
Knot, prime, stop and paint one coat oil colour on general surfaces of woodwork	Yd. super	3/6	1/5 1/2
Ditto on skirtings, rails, frames, etc., not exceeding 3" girth	Yd. run	-/5 1/2	-/2
Ditto ditto for each additional 3" in girth	"	-/5	-/2
Ditto on sash squares one side	Dozen	4/9	1/10
Ditto on large sash squares one side	"	8/6	3/3

Stain and Varnish on Wood

Prepare, size, stain and twice varnish on general surfaces of woodwork	Yd. super	3/11
Ditto on skirtings, rails, frames, etc., not exceeding 3" girth	Yd. run	-/6
Ditto ditto for each additional 3" in girth	"	-/5 1/2

J. A. Davis

F.R.I.C.S., F.I.Arb.

Interior Partitioning?

INSULATION BOARD CORE,
FACED BOTH SIDES HARDBOARD

CORK CORE,
FACED RESIN BONDED BIRCH PLY

RESIN BONDED
PINE CORE BLOCK BOARD
GABOON FACED

CORK CORE, BOTH SIDES ALUMINIUM
—LIGHT WEIGHT ; FOR HEAT AND
ACOUSTICS INSULATION

ASBESTOS CORE FACED BOTH SIDES
WITH GALVANIZED STEEL
APPROVED FIRE-PROOF PARTITIONING

Have you a problem?

Can we help to solve it? We specialize in the manufacture
of composite materials suitable for any type of partitioning. Our technical services are at your disposal.

**William Mallinson
and Sons Ltd.**

TIMBER AND VENEER MERCHANTS
MANUFACTURERS OF PLYWOOD, ARMOURPLY, PANELS, COMPOSITE PARTITIONING AND INSULATING BOARDS

130-150 HACKNEY ROAD
LONDON, E.2

Telephone: Shoreditch 7654 (10 lines)


Telegram: "Almoner," London



HAYMARKET HOUSE · HAYMARKET · LONDON · S.W.1
 Architects: E. A. Stone, Toms & Partners, London, W.1.
 Contractors: Geo. Wimpey & Co., Ltd., London, W.6.
 Electrical Contractors: Berkeley Electrical Engineering Co., Ltd.,
 London, S.W.1.

UNDERFLOOR CABLE DUCTS

by



GREENWOOD-AIRVAC

Greenwood-Airvac conduit system was installed in Haymarket House—one of the many new buildings so equipped.

The publication 'Greenwood-Airvac Conduit Systems' tells you more about Greenwood-Airvac cable ducts. Please write for a free copy.

GREENWOOD'S AND AIRVAC VENTILATING CO., LTD.
 BEACON HOUSE · KINGSWAY · LONDON · W.C.2.
 CHANCERY 8135 (4 lines)
 AIRVAC—LONDON



*A Specialist Service
 for design...*

...for supply

BURN BROS
 (LONDON) LIMITED

Cast Iron pipes & fittings

We design and supply, for home and abroad, installations for plumbing, drainage, and sewage pumping and disposal plants. Consultation before plans are settled can reduce costs and avoid delays. Large stocks, covering a wide range, support this important service with good deliveries. Please ask for our catalogue.



**RAINES
& PORTER
LIMITED**

dependable products

**enamels
distempers
varnishes
paints**

SYNTHO-FLEX

Synthetic Gloss Finishing Paint

PUROL-FLEX

Guarantee Gloss Paint

SUPERGLOS

Enamel Finishing Paint

UNDERCOATING

For above Gloss Finishes

RAINES OIL FLAT

A perfect Flat Finish

VELMATT GLAZE

Transparent glaze colour

VELTEX

Plastic Relief

VELSET

Emulsion Paint

VELSTONE

Imitation Stone Paint

MURADEK

Oil Bound Washable Water Paint

Head Office & Works:

LONDON

BOWLES ROAD, S.E.1
Tel Bermondsey 2575

TRANBY WORKS, WINCOLMLEE, HULL Tel. 34683

NEWCASTLE-ON-TYNE

28 LEAZES PARK ROAD
Telephone 27890

GLASGOW

CUMBERLAND LANE, C.5
Tel. South 1896



THE MIDLAND WOODWORKING CO. LTD. MELTON MOWBRAY

Specialists in high class Standard Joinery for the Building Trade

AP/MW.12

Important revisions of British Standards for Lead Pipe

Many permissible minimum weights greatly reduced

B.S.602 **B.S.1085**
FOR LEAD PIPE FOR SILVER-COPPER-LEAD ALLOY PIPE

are both revised

Tables incorporating the new standards have been prepared and are available in a revised edition of "CONCISE INFORMATION ON LEAD PIPE" free on request.



LEAD SHEET AND PIPE COUNCIL

In association with LEAD DEVELOPMENT ASSOCIATION

EAGLE HOUSE · JERMYN STREET · LONDON · SW1

Telegrams: Ukleadman, Piccy, London Telephone: Whitehall 4175


B.124

Freedom with Certainty

FREEDOM in design, for
brick offers almost unlimited
scope for interesting effects...

CERTAINTY of a pleasing
and lasting result, for brick
imparts an attractive finish of
exceptional durability.

*Good supplies of Brick
are now available
in all areas.*




Hassenbrook Secondary School, Stanford-le-Hope, Essex. Designed by Gerald Lacoste, M.B.E., F.R.I.B.A., in association with Harold Conolly, F.R.I.B.A., County Architect
Assistant Architects: Kenneth Dod and Campbell Ross, A.R.I.B.A.

BRICK

for Modern Building

Issued by The National Federation of Clay Industries. Drayton House, London, W.C.1.



ZINC DUST ... for Paints



Corrosion is especially dangerous under water. Another example of protective painting is the rudder of the oil-tanker 'Caprinus' which is painted with highly metallic Zinc rich paint.

IMPERIAL SMELTING
U.K. MEMBER OF THE CONSOLIDATED ZINC CORPORATION LIMITED

For mechanical protection and electro-chemical defence—against CORROSION

Corrosive conditions demand positive action. Only a zinc metal coating gives maximum protection to iron and steelwork. Zinc rich paint provides this vital protection; its action is electrolytic; even if the paint film should be damaged the underlying metal is still protected by the adjacent zinc particles and the spread of corrosion is arrested. Zinc rich paint is non-toxic and is applied with ease whether for new work or for renovating.

Specify a zinc dust from the Imperial Smelting range for use in your zinc rich paint formulations. We will gladly supply a list of zinc dust paint manufacturers on application.

IMPERIAL SMELTING CORPORATION (SALES) LIMITED · 37 DOVER STREET · LONDON W.1

cut

this

out!

Can you afford to waste money by using outdated construction methods?

Take a look at the illustration on the right. All the costly shaded items are replaced by the one simple Finlock Gutter Unit shown below, with lintel cast in situ in the patent rear trough. Maintenance costs? There are *none*.

If you have not seen the Finlock technical literature yet, why not send for it today? It covers the five types of gutter, the hot bitumen and aluminium lining service and the Finlock Sprocket. It all adds up to

better building at lower costs.

and you
save all
the way
round

FINLOCK

FINLOCK GUTTERS LIMITED

Finlock House, Frant Road, Tunbridge Wells, Kent. Telephone: Tunbridge Wells 3396/9

Works at : Southborough, Kent; Royston, Herts; Cwmbran, S. Wales; Crewkerne, Somerset; Leeds, Yorks; Wakefield, Yorks; Musselburgh, Scotland; Belfast, N. Ireland

DHB/3499

And now—

Copper Tubes from Kirkby

The whole range of I.C.I. copper tubes is now being made at Kirkby Works, near Liverpool—the largest copper tube mill in the British Commonwealth. Kirkby's main mill—more than seven acres under one roof—is the largest single production unit in the British non-ferrous industry and houses the

most powerful tube-drawing machinery in the world.

I.C.I. copper tubes have long played a leading part in every branch of engineering. With the improved production methods at Kirkby, I.C.I. is able to offer even better service to industry at home and abroad.

COPPER TUBES for gas, water and waste services, radiant panel heating, locomotives' and ships' services, refrigerators, chemical and general engineering.

IMPERIAL CHEMICAL INDUSTRIES LIMITED, LONDON, S.W.1




M288

Sooner or later you will come across something that could be made lighter, more durable, or more quickly and economically in aluminium.

That's the moment to talk it over with an experienced man from

Northern Aluminium*



Constructors: Aluminium Construction Ltd., Woking.

Proof in this Roof

When the time came to replace the badly spalled concrete glazing frames on the roof of the Leyton Public Baths, the engineers concerned chose Noral 50SWP alloy for the job. Why? Because—as with so many other jobs—Noral alloys were ideal for the purpose, being light, strong, and needing a minimum of maintenance during long years of service, and being free from spalling.

One 13 ft. by 8 ft. panel of the aluminium framework weighs only 2 cwt. and is flexible enough to be shaped, on site, to the slight convex curve of the roof without preforming. Yet the assembly is strong enough to carry a snow loading of 30 lb./sq. ft. in addition to the dead load of 1-in.-thick glass paving bricks, and workmen were able to walk safely on the framework. The total glazed area of the roof is about 5,700 sq.ft.

Aluminium patent glazing bars and window frames such as these have been in use in many buildings for over a quarter of a century and are still good for many more years. They are quick to install, and the intricacy of the cross-sectional shapes obtainable offers scope for new approaches in design.

If you have any specific problem regarding the use of aluminium in building, please write to our Sales Development Division, Banbury, Oxon.


Northern Aluminium

C O M P A N Y L I M I T E D

An ALUMINIUM LIMITED Company



when it's a question of flooring



RILTILE
Thermoplastic Flooring


RILTILE is the complete answer, being an ideal combination of all those properties long sought for in flooring. The outcome of intense research based upon long experience, this thermoplastic hard tile is recommended with every confidence for use in hospitals, kitchens, bathrooms, offices, shops, bars, restaurants

RILTILE is made in tiles only, measuring $9'' \times 9'' \times \frac{1}{4}''$, in a wide range of colours and mottled effects and at a cost to compare favourably with good quality inlaid linoleum. Damp proof, heat insulating, with excellent resilience, **RILTILE** is also impervious to dilute acids, alkalis, and is resistant to hot and cold water. It should be noted that only 12 hours are required after laying, before the floor is ready for normal traffic. While not completely fireproof, the asbestos used in the manufacture of **RILTILE** gives it excellent fire-resisting qualities.

Extremely hard wearing ☐ Easily and quickly laid
 Reduces foot fatigue ☐ No special cleaning required


Write for samples and illustrated brochure—

BRITISH MOULDEX LTD • MOULDEX HOUSE • 27/29 Fitzroy Street, London, W.1 • Tel: LAngham 4211/2



Siegwart beams are precast at Siegwart works under expert supervision and controlled production methods. They are delivered to the site ready for placing straight into their planned positions thus avoiding delays or interference with construction programmes.

SIEGWART PRECAST FLOORS AND ROOFS



Modern Power Station at Poole, Dorset. Central Electricity Authority, Southern Division

SIEGWART FLOOR COMPANY LIMITED

GABLE HOUSE, 40 HIGH STREET, RICKMANSWORTH, HERTFORDSHIRE
AND AT BIRMINGHAM, LEICESTER, MANCHESTER AND GLASGOW



**How
CATESBYS lino
cured
cold feet**

Somebody rang Catesbys recently to say that a refrigeration plant on the floor below was making life pretty chilly for the people in the offices above. Could Catesbys, as floor covering specialists, do anything about it?

Catesbys could and did.


Our craftsmen fitted a thick cork carpet for insulation and heavy-weight Lino on top for wear. The difficult problem of fixing so thick a

covering was solved by a rather special Catesby method—born out of 60 years experience in lino. Now the office is not only cosy and quiet, but remarkably comfy underfoot. Which only goes to show what Catesbys—and Lino—can do for you.

Catesbys Linoleum Contracts

TOTTENHAM COURT RD • LONDON • W1 • MUSEUM 7777

**specialists in
the design,
fabrication and
erection of
structural
steelwork**



- 1** New factory building for Messrs. William Cooke & Sons of Rotherham. 300 ft. x 120 ft. span.
- 2** The County Primary School, Crosland Moor, Huddersfield.
- 3** College of Further Education, Grimsby, in course of erection.
- 4** The completed College.

**Structural Steelwork
by AUSTINS**



JAMES AUSTIN & SONS
(Dewsbury) LTD

STRUCTURAL ENGINEERS · DEWSBURY · YORKSHIRE

Telephone: 1750 (7 lines).

Telegrams: AUSTINS DEWSBURY TELEX.

Associated Companies:



ASTLEY BROOK & CO. LTD., ST. GEORGE'S WKS., HUDDERSFIELD

A. J. RILEY & SON LTD., VICTORIA WORKS, BATLEY




Contemporary Time by SMITHS

IN A READING ALCOVE
OF A MODERN SCHOOL



BEDFORD

'Sectric' wall clock, surface or flush fixing, in ice birch finish case. Applied bronze numerals. Overall diameter 18" £18.2.2.




ADELPHI

'Sectric' wall clock in moulded ivory or walnut finish case. Minor, 5½" dial, £4.4.6. Medium, 9" dial, £6.9.10. Major, 12" dial, £7.10.11.

From being commonplace, the clock today plays an increasingly important part in the decorative scheme of things, no matter what the architectural character of its surroundings. Smiths extremely wide range of models, from which the clocks illustrated are drawn, gives a wide choice. It may not be generally known by Architects, however, that their own individual designs can be carried out in any medium. At any time a representative will be pleased to discuss your requirements.

A
'SMITHS OF ENGLAND
PRODUCT

SMITHS CLOCKS & WATCHES LTD., LONDON, N.W.2. A Division of S. Smith & Sons (England) Ltd.



*Craftsmanship
comes the hard way...*

If nearly 90 years spent in the design, fabrication and erection of structural steelwork means anything—it means you can place this work in our hands knowing it will progress smoothly to completion. Big job or small job, at home or overseas, we have the resources to handle all your needs. We welcome the opportunity of serving you.

Established 1867

WALKER BROS
LIMITED
Structural Engineers

Craftsmen in steel

WALSALL STAFFS. Tel: WALSALL 3136
London Office: 66, Victoria St., S.W.1. Tel: VIC 3926

WE HAVE AN EXHIBIT AT
THE BUILDING CENTRE

26 STORE STREET-W.C.1




This new 'Easilyne' Bath Mixer (No. 5326 ELM) with overhead shower is the natural successor to our 'telephone' mixer (No. 5312 ELM) which was exhibited and advertised during 1955.

Delivery is not immediate — but here, we feel, is a fitting that is really worth waiting for! We look forward to your enquiries.

Sanbra Ltd

ASTON HALL ROAD · BIRMINGHAM, 6

Designers and Manufacturers of a complete range of fine-quality Plumbers' Brassfoundry



Visit the Shell and BP Display

'OIL FUEL IN INDUSTRY'

At the Factory Equipment Exhibition, Earls Court, 9-14 April

OIL FUEL IN INDUSTRY, the Shell and BP display, is the central feature of the Factory Equipment Exhibition at Earls Court this year. It covers 12,000 square feet of floor space and is the largest display of its kind ever assembled in this country.

Shell-Mex and B.P. Ltd., in co-operation with many equipment manufacturers and the Factory Equipment Exhibition organisers, are staging a comprehensive

display of oil-burning equipment for space heating, steam raising and other factory heating processes. This is the chance of a lifetime. It may be many years before there is another opportunity to see such an interesting and informative display on the subject of oil-fired heating—the most effective, flexible and labour-saving form of heating now available to British Industry.

IMPROVED MODERN HEATING APPLIANCES DESERVE BETTER FLUES

Better flues are achieved with the **Finch Throat Unit**



Faulty design at the entrance to the flue can waste heat, cause smoky fires and damage to surrounds. The Finch Throat Unit overcomes these problems by providing a smooth, streamlined union between the fire and flue. In this way, the smoke column is given extra velocity, down draughts are reduced and a protective insulating void is provided between the throat and the surround.

The restriction provided by the unit reduces excessive ventilation in the room. Recent practical tests have proved that the installation of the Throat Unit actually gives a room-heat conservation figure of 17% plus, over and above the saving made by the modern appliance.

These very practical advantages make the Finch Throat Unit an essential part of every fireplace installation.

THE *Finch* ORGANIZATION

Head Office & Works:

BELVEDERE WORKS, BARKINGSIDE, ESSEX VAleNTine 8888 (30 lines)

Showrooms:

FINCH CORNER, 679/687 EASTERN AVENUE, ILFORD, ESSEX


A comprehensive work on flue design entitled "The Finch Chimney Throat Unit" is available free on request.

CRAFTSMANSHIP

in
traditional
and modern
materials



*Lift Panelling at
Mount Royal, W.1.*



*A modern bar at the "Apple Tree", Crawley.
Architects: Godman & Kay, F/R.I.B.A.*

THE specialised services of Permatops Ltd. have been associated with numerous important contracts for the internal equipment and embellishment of buildings.

The Company is now owned by Anderson Construction Co. Ltd. and its activities are under the direct control and management of A.C.C.

This combination of experience, fabrication techniques and resources enables more comprehensive service to be rendered in the sphere of

SPECIALIST FITMENTS, BUILT-IN CABINET WORK,
DECORATIVE CLADDING

and the refurbishing of interiors with modern sheet material.

ENQUIRIES ARE INVITED.

permatops

PERMATOPS, LTD

A subsidiary of Anderson Construction Co. Ltd.


CLIFTON HOUSE, EUSTON ROAD, LONDON, N.W.1.

Telephone: EUSon 7465

Factories at Wandsworth and Southgate

The Company's operations cover a wide field, embracing the construction and installation of:—

Bathroom Fitments	Service Counters
Bar Counters	Wall Panelling
Food Counters	Dado Panelling
Lift Linings	Kitchen Equipment
Escalator Linings	Flush Doors
Reception Counters	Hospital Fitments
Laboratory Benches, etc., etc.	




There's always another use for gas

There's always another use for gas...

...for heating liquids


From swimming bath water to salt bath solutions, gas heating has no rival. Gas goes to work rapidly and is simple to operate. Whatever the quantity, whatever the liquid, it burns clean and constant to give you the precise heat you require.



Gas-fired boilers

...for heating air

Practically any problem requiring heated air can be solved by gas whether it is for space heating, drying or for industrial processing.




Room heating

...for 'Operation Rescue'

Gas can play an important part in improving housing conditions. Costs are kept low by use of existing gas supplies and absence of elaborate structural work. Gas adaptability is particularly suitable to the conditions found in 'Operation Rescue' properties, and, of course, the popularity of gas for water heating and cooking is unquestioned.

Apart from its smokelessness and cleanliness, gas gives you infinite, accurate and automatic controllability at every stage. Supply is assured and constant calorific value is guaranteed. And gas saves because it needs no stoking or storage space.



'Operation Rescue'



Consult your area gas board

The Gas Industry makes the best use of the Nation's coal


ISSUED BY THE GAS COUNCIL

GCGE33-

PLIMBERITE BUILDING BOARD

Size: 8 ft. x 4 ft.

Thicknesses: $\frac{1}{2}$ in. & $\frac{3}{4}$ in.



Office Partitioning for POWERS-SAMAS

The PLIMBERITE REBOND Partitioning System was installed by Compactom Limited of Oxgate Lane, Cricklewood, London, N.W.2, in the new Croydon offices of Powers-Samas Accounting Machines Limited.

The photograph shows typical construction with and without glazing. Working details for the construction of double-skin demountable partitions are given in the PLIMBERITE REBOND BOOKLET.

The PLIMBERITE Technical Brochure deals in detail with the methods of construction when using PLIMBERITE for

Wall lining
Single-skin partitioning
Double-skin partitioning
Flooring over joists
Flooring over a sub-floor

Roof decking, flat or pitched
Fitted cupboard work
Shopfitting
Furniture making
Concrete shuttering

For technical publications on PLIMBERITE, samples, prices, and the name and address of your nearest main Distributor, write to:

BRITISH PLIMBER LIMITED

19 Albert Embankment, London, S.E.11





PLIMBERITE BUILDING BOARD

LEEDS 'IMPERIAL PORCELAIN' FIRECLAY

The strength and high resistance to thermal shock of "IMPERIAL PORCELAIN" FIRECLAY SANITARY WARE are a guarantee of long life in service.

"IMPERIAL PORCELAIN" FIRECLAY SANITARY WARE outlasts all other types and proves that the best is cheapest in the long run.

All the resources of England's largest organization manufacturing Fireclay Sanitary Ware stand behind the product.



PRODUCTS OF THE

Leeds Fireclay GROUP OF COMPANIES

WORTLEY, LEEDS 12. Tel. LEEDS 638021

LONDON OFFICE: LEEDS HOUSE, CAVENDISH PLACE, LONDON, W.1.

Telephone: LANGham 3511.

Telegrams: FIRECLAY WESDO LONDON

Cogent

Hangers
PAINT MAKERS SINCE 1872

The Ideal
Combination

FABRIGUARD
(REGD)

Emulso Plastic Paint. Dries rapidly on plaster surfaces even when new. Resists new surface alkalis; proof against petrol, oil and bleeding of bitumen or creosote. Fire retarding. Forms a coherent, rubber-like film, washable a day after application.



Butlin's Ocean Hotel, Brighton

Balanced, alkyd, hard gloss enamel paint, evolved from close study of media/pigment ratio. A durable coating resistant to steam, moisture and sea air. Write for details.


& Floralac

HANGERS PAINTS LTD. HULL


Also LONDON . LIVERPOOL . BIRMINGHAM . GLASGOW . TORQUAY & NORWICH

To get you out of **HOT WATER** *Troubles*

Specified by
Local Authorities,
Architects and
Heating Engineers
throughout the
country.



DURHAM



CALORIFIER

ROLYAT PATENT HOT WATER TANKS

THE ROLYAT TANK CO. LTD. • CROMWELL ROAD • YORK

*the
unique
features of*
**ROBERTSON
Q-DECK**
TRADE MARK
include...



The flanged and bolted side joints of Q-Deck units minimise fire hazard. Deck units cannot separate and so a barrier to fire spread is maintained so long as the structural supports remain in position. Details of side and end laps are illustrated on page eight of Q-Deck Publication QD3. *Have you had your copy?*

- ✓ fire risk minimised
- ✓ flat, clean soffit
- ✓ permissible spans up to 14 feet
- resistance to corrosive conditions
- 'top speed' fixing
- no blistering of felt weatherproofing



**FIRE
RISK
MINIMISED**


ROBERTSON THAIN LIMITED
Ellesmere Port • Wirral • Cheshire

Telephone: Ellesmere Port 2341
Telegrams: "Robertroof"

Sales Offices:

LONDON
GLASGOW
BELFAST
BIRMINGHAM
NEWCASTLE
LIVERPOOL
SHEFFIELD
MANCHESTER
CARDIFF





An end to a winter worry

Water pipes of 'Shirene' never burst however hard the frost

With 'Shirene' plastic tubing, burst water pipes are now a thing of the past. Although so tough as to be **virtually indestructible**, 'Shirene' has sufficient "give" to accommodate the pressure of water turning to ice. Think of the damage and inconvenience property owners and householders will be saved. 'Shirene' is also much cheaper than conventional piping. Flexible, many times lighter than metal and far easier to work, it takes a big load off the plumber's shoulders. Builders' and plumbers' merchants too will find they're on to a good thing with 'Shirene'. Additionally, 'Shirene' is the perfect medium for agricultural supply lines, industrial or chemical plumbing, and all kinds of cold liquid conveyance. It is non-toxic, and quite unaffected by most acids, alkalis, salt water, air or soil.

White or colours can be had in a wide range of standard sizes up to 12". Larger sizes specially made. Coils of 50', 100', 250', and up to 500', each wrapped in hessian and labelled with full details. Immediate delivery of all standard sizes in all coil lengths.



'Shirene' is a product of Shires, the largest manufacturers of moulded cisterns in Europe. For full details and trade terms write to:

DEPT. A.I. SHIRES & CO. (LONDON) LTD.,
GREENBOTTOM WORKS, GUISELEY, YORKS.
(Factories also at London and Stoke)
Shires (Ireland) Ltd., Stannaway Drive, Crumlin, Dublin.



AHLSTRÖM

five three

the hardboard with the extra width

Enquire from your local merchants or from
Plywood & Timber Products Agencies Ltd.
City-Gate House, (East), Finsbury Square, E.C.2

Manufactured by A. AHLSTRÖM OSAKEYHTIÖ, FINLAND



Where first cost is not a primary consideration, the aluminium window has much to commend it. Indeed, when sliding sashes are required, aluminium is the logical — and perhaps the only entirely suitable — material. For the window which, year in and year out, must move at a touch should be built to the closest possible limits of accuracy. And for such a window, aluminium offers one further life-long advantage — its sliding surfaces need neither lubrication nor paint protection.

The Beacon Double-Hung Sash Units, installed in the new Lamp Works Offices of The British Thomson-Houston Co. Ltd., Rugby, and shown above, are typical of a number of similar purpose-made installations produced at our Bilston Works. The services of our experienced team of designers and engineers will be made available to all Architects and others engaged on any project requiring Metal Windows or Wall Cladding.




Member of the  Metal Window Association

JOHN THOMPSON BEACON WINDOWS LTD - WOLVERHAMPTON

**I'VE KNOWN 'EM
FOR TWENTY
YEARS AND
THEY'VE
ALWAYS
BEEN GOOD**



Fordhams are styled to today's tastes, pressed from a single sheet of steel, and fitted with the famous syphonic mechanism with fewer moving parts than any other cistern. No wonder they are in such demand. Send today for the fully illustrated colour sheets showing the entire range of favourite Fordhams.




**THAT'S WHY I STILL PREFER TO
FIT A *Fordham***

FORDHAM PRESSINGS LTD • DUDLEY RD • WOLVERHAMPTON • TEL: 23861

33% floor space saved 25% more desk area

846 (Eight-for-Six) furniture literally applies time and motion principles to the office—whether it is for one person or several hundred (including sound-proofed offices for Senior Personnel). Thus *eight* people can work with greater efficiency and comfort where only *six* worked before.

And in addition the desk area of each worker is 25% greater. Plan NOW for future expansion—decide to make more of existing space. 846 (Eight-for-Six) is efficient! It *looks* efficient too! Just write "846" (Eight-for-Six) on your notepaper and full particulars will be sent by return.



Send for this fully illustrated free booklet showing wide variety of seating plans.




Shannon Systems

THE SHANNON LTD., 28 SHANNON CORNER, NEW MALDEN, SURREY

846
EIGHT-FOR-SIX

**SERIES
System OFFICE
FURNITURE**





61

a

46
07-



To Architects about to plan Roofs

Speedy Erection



**72,000 Sq. ft.
of BITUMETAL
laid in
14 weeks**



*Barras Heath Wholesale Market—
Coventry.
Designed by Coventry City Architect.*

When you require a roof quickly erected yet with the advantages of permanence, high thermal insulation, virtually no maintenance, and an attractive ceiling too, plan for BITUMETAL.

How is this speed attained?

1. BITUMETAL Aluminium Units arrive on the site in prefabricated form.
 2. Each roof is planned by a staff of experienced roofing technicians, and laid by capable workmen.
- Moreover, a BITUMETAL Roof can be laid long before interior work is underway. This ensures dry working conditions for other trades.

Ask our nearest Area Manager for the latest information on BITUMETAL Roofing Technique.



ROOF


plus **CEILING**
plus **INSULATION**

WILLIAM BRIGGS & SONS LIMITED
LONDON: VAUXHALL GROVE, S.W.8 Regd. Office: **DUNDEE**
OFFICES & DEPOTS ALSO AT ABERDEEN · BELFAST · BRISTOL · DUBLIN
EDINBURGH · GLASGOW · LEICESTER · LIVERPOOL · NORWICH



FERODO Stairtreads

Quickly available in seven colours and twenty-two shapes



FERODO

You can have rapid delivery of Ferodo Stairtreads, for use in public buildings, offices, hotels etc. Ferodo Stairtreads wear extremely well. One set at the University Union, Manchester withstood 33 years' continuous use before renewal!

Colours

Ferodo composition gives a non slip surface in a wide range of colours: red, white, blue, green, black, brown or grey. Ferodo Fabric is also available in dark brown. There is a choice of nosing colours too; aluminium, manganese bronze & silver bronze.

Patterns and dimensions

Here are only three of the 31 types and sizes of stairtread. This very wide range of patterns comes in lengths up to 13'6" and curved treads are available for steps with specially shaped ends.

There is also a plain, steelbacked stairtread for warehouses, factories etc.

Fitting and maintenance

Ferodo stairtreads are ready drilled and the special "secret fitting" feature ensures that retaining screws do not show. The treads may be backed with good quality linoleum or other flooring materials. The treads are easily cleaned, and need no other maintenance. Ferodo Stairtreads combine good appearance and safety with economy. For full details, prices and reference numbers for easy ordering, send for Ferodo Stairtread Catalogue No. 925.

Non-slip Stairtreads

FO

INGL

availab
11"; cl
9".

FROM

• Up
door
• Easil
• Port
• Fire
• Non-
alloy

NOW
EXCL
NEW
DES

63.



BATLEY CONCRETE GARAGES

FOR EVERY CAR—AND EVERY SITE!

SINGLE GARAGES

Available in widths of 8' 3" or 11'; clear height of 6' 3" or 9'. Extendible in length.

FROM £49/10/- OR 10/- WEEKLY




'Up and Over' or hinged doors available.
Easily erected.
Portable yet permanent.
Fireproof and rotproof.
Non-corrosive aluminium alloy bolts and fittings.

LEAN-TO GARAGE Designed for building on to the house or existing wall. Width required only 8'. Rear door available

FROM £50 OR 10/- WEEKLY

MULTIPLE GARAGES. One, two or more supplied in a block. Will provide an unequalled investment.

FROM £55 OR TERMS



NOW WITH
EXCLUSIVE
NEW ROOF
DESIGN

Attractive Deferred Terms
FIVE YEARS' FREE FIRE INSURANCE
Free Delivery in England and Wales

Send for FREE Illustrated Brochure
ERNEST BATLEY LIMITED

63, Colledge Road, Holbrooks, Coventry. Tel.: 89245/6




Write for full details to:—

ECONA MODERN PRODUCTS LIMITED
AQUA WORKS · HIGHLANDS ROAD · SHIRLEY · BIRMINGHAM
Telephone & Telegrams: Solihull 3078.

specify
'purpose made'
windows & doors
for modern projects

Our experts are at your service in a free advisory capacity—at the very earliest stages

"modest flag wavers for nearly 40 years"



St. Nicholas Grammar School, Northwood Hills, (Middlesex County Education Committee)
C. G. Stillman Esq., F.R.I.B.A., Architect

PURPOSE MADE METAL WINDOWS AND DOORS · STANDARD METAL WINDOWS AND DOORS—with or without wood surrounds
PURPOSE MADE AND STANDARD INDUSTRIAL SASHES · STEEL INTERNAL PARTITIONING · ROOF AND SIDE WALL PATENT GLAZING · LANTERN LIGHTS AND DECK LIGHTS · PRESSED STEEL DOOR FRAMES · CURTAIN WALLING

STANDARD


THE STANDARD METAL WINDOW CO.

Head Office and Works:

HOUGHTON ST., WEST BROMWICH

Telephone: WEST BROMWICH 0405

Fully illustrated literature available on request.



London Office:

36 HIGH HOLBORN, LONDON, W.C.1.
Telephone: CHANCERY 2233


Worthing Office:

30 MANOR ROAD, WORTHING.
Telephone: 7495

North Staffordshire Office:

MORETON HOUSE, WOLSTANTON,
NEWCASTLE, STAFFS.
Telephone: STOKE ON TRENT 87207

Scheme in Progress



Picton Street Development

An interesting departure in design and construction practice characterises the London County Council scheme at Picton Street, Camberwell, for 682 dwellings in maisonettes, flats, and terrace houses. The Company was nominated as contractor at the planning stage of the project, fourteen months before commencement of work on the site, working with the architect, consulting engineer and others in a design team.

In this way knowledge of new or alternative materials, component handling, and erection techniques, was available at the time when it could most profitably be used, and together with the Company's facilities for research and development has contributed in determining the final design.

*Architect to the London County Council
Dr. J. L. Martin, M.A., F.R.I.B.A.*

LAING

JOHN LAING AND SON LIMITED, GREAT BRITAIN, CANADA, UNION OF SOUTH AFRICA, RHODESIA

